					CONSTRUCTION CODE								
					80% FED 20% STATE	100% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% JOLIET	100% JOLIET	100% JOLIET	80% FED 20% STATE	80% FED 20% STATE
							RAMP B	RAMP D	VOYAGER LN.	RAMP B	RAMP D		
					ROADWAY 0004	ROADWAY 0004	TRAFFIC SIGNALS 0021			EVP 0021		INTER-CONNECT 0021	STREET LIGHTING 0021
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	14			7	7					
•	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	1,378						678	700		
	X0326767	PROFILE DIAMOND GRINDING CONCRETE PAVEMENT	SQ YD	616	616								
•	X0327349	TEMPORARY WOOD POLE, 40 FT., CLASS 4	EACH	2									2
	X2511630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	2,875	2,875								
	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	29		29							
	X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	75		75							
	X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	119		119							
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1								
•	X8210040	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT (HORIZONTAL MOUNT)	EACH	9									9
•	X8570215	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	1					1				
•	X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2			1	1					
•	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	3			1	1	1				
•	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	6,895								6,895	

• SPECIALTY ITEM

FILE NAME = S:\JDL\6320-6379\6346\DGN\Micro\A1060 Sheets\6W13-sht-000.dgn

STRAND ASSOCIATES
1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = GillP	DESIGNED - JLB	REVISED -
MODEL NAME = Defaults	DRAWN - DJW	REVISED -
PLOT SCALE = 2.2020 ' / in.	CHECKED - BMA	REVISED -
PLOT DATE = 12/23/2013	DATE - 12/17/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14-N	WILL	163	16
		CONTRACT NO. 60W13		
	ILLINOIS FED. AID PROJECT			