SIGN INFORMATION			EXISTING SIGN SCHEDULE										PROPOSED SIGN SCHEDULE											
			EXISTING LOCATION			EXISTING SIZE		REMOVE					PROPOSED LOCATION			PROPOSED SIZE		INSTALL						
SIGN #	DESCRIPTION	DESIGNATION	STA.	OFFSET L/R	SUPPORT TYPE	WIDTH (FT)	HEIGHT (FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	REMOVE GROUND MOUNTED SIGN SUPPORT (EACH)	REMOVE CONCRETE FOUNDATION - GROUND MOUNT (EACH)	STA.	OFFSET L/R	SUPPORT TYPE	WIDTH (FT)	HEIGHT (FT)	SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FT)	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	RELOCATE SIGN PANEL - TYPE 3 (SQ FT)	RELOCATE GROUND MOUNTED SIGN SUPPORT (EACH)
RB-GM-100	LODGING	Specific Service	12+12.00	20.2 RT	GROUND MOUNT	12.0	8.0			96	2	2	12+00.00	20.0 RT	GROUND MOUNT	12.5	5.5			68.75		•		
RB-GM-101	FOOD	Specific Service	14+14.00	28.6 RT	GROUND MOUNT	12.0	8.0			96	2	2	14+00.00	30.0 RT	GROUND MOUNT	14.0	5.5			77		•		
RB-GM-102	GAS	Specific Service	16+14.00	25.7 RT	GROUND MOUNT	9.5	5.0			47.5	2	2	16+00.00	46.0 RT	GROUND MOUNT	14.0	5.5			77		•		
RB-GM-103	ADVANCED INTERSECTION LANE CONTROL	R3-8x	17+99.00	29.5 LT	GROUND MOUNT	4.0	2.5		10		1		21+00.00	35.0 LT	GROUND MOUNT	6.0	2.5		15		29.00(2)			
RB-GM-104	ADVANCED INTERSECTION LANE CONTROL	R3-8x											21+00.00	52.0 RT	GROUND MOUNT	6.0	2.5		15		29.00(2)			
RB-GM-105	DESTINATION	Specific Service	20+56.00	33.1 RT	GROUND MOUNT	7.0	6.0			42	2	2	19+50.00	52.0 RT	GROUND MOUNT	5.0	2.5		12.5		29.00(2)			
RB-GM-106A	PARK AND RIDE	D4-2	21+02.00	35.1 LT	GROUND MOUNT	2.5	4.0		10		1		20+00.00	30.0 LT	GROUND MOUNT	2.5	3.0	7.5			15.00			
RB-GM-106B	A.I.S.		21+02.00	35.1 LT	GROUND MOUNT								19+00.00	30.0 LT	GROUND MOUNT	4.5	3.5		15.75		31.00(2)			
RB-GM-107	WRONG WAY	R5-1a	21+02.00	35.1 LT	GROUND MOUNT	3.0	2.0	6			1		21+00.00	35.0 LT	GROUND MOUNT	3.5	2.5	8.75			••			
RB-GM-108	DO NOT ENTER	R5-1	22+56.00	27.0 RT	GROUND MOUNT	3.0	3.0	9			1		22+80.00	52.0 RT	GROUND MOUNT	4.0	4.0		16		32.00(2)			
RB-GM-109	DO NOT ENTER	R5-1	22+58.00	33.8 LT	GROUND MOUNT	3.0	3.0	9			1		22+80.00	35.0 LT	GROUND MOUNT	4.0	4.0		16		32.00(2)			
RB-GM-110	RIGHT TURN PROHIBITION	R3-1	23+07.00	85.8 LT	GROUND MOUNT	3.0	3.0	9			1		23+07.00	85.8 LT	GROUND MOUNT	3.0	3.0	9			•••			
RB-GM-111	KEEP RIGHT	R4-7	23+57.00	95.2 LT	GROUND MOUNT	2.0	2.5	5			1		23+57.00	95.2 LT	GROUND MOUNT	2.0	2.5	5			•••			
RB-GM-112	KEEP RIGHT	R4-7	23+57.00	16.1 RT	GROUND MOUNT	2.0	2.5	5			1		23+57.00	16.1 RT	GROUND MOUNT	2.0	2.5	5			•••			
RB-GM-113	I 55 SOUTH	Destination	22+90.00	68.1 LT	GROUND MOUNT	12.0	8.0			96	2	2	22+90.00	85.5 LT	GROUND MOUNT								96.00	1.00
RB-GM-114	WRONG WAY	R5-1a											21+00.00	52.0 RT	GROUND MOUNT	3.5	2.5	8.75			••			
RB-GM-115	ONE WAY	R6-1											22+80.00	35.0 LT	GROUND MOUNT	3.0	1.0	3			••			
RB-GM-116	ONE WAY	R6-1											22+80.00	35.0 LT	GROUND MOUNT	3.0	1.0	3			••			
RB-GM-117	NO TURN ON RED EXCEPT RT LANE	R10-11C											23+57.00	16.1 RT	GROUND MOUNT	2.5	3.5	8.75			•••			
RD-GM-200	FOOD	Specific Service	16+54.00	47.5 RT	GROUND MOUNT	12.0	8.0			96	2	2	16+50.00	41.5 RT	GROUND MOUNT	14.0	5.5			77		•		
RD-GM-201	GAS	Specific Service	18+60.00	45.0 RT	GROUND MOUNT	9.0	8.0			72	2	2	18+50.00	46.5 RT	GROUND MOUNT	14.0	5.5			77		•		
RD-GM-202	ADVANCED INTERSECTION LANE CONTROL	R3-8x											20+00.00	24.0 LT	GROUND MOUNT	4.5	2.5		11.25		29.00(2)			
RD-GM-203	ADVANCED INTERSECTION LANE CONTROL	R3-8x											20+00.00	52.0 RT	GROUND MOUNT	4.5	2.5		11.25		29.00(2)			
RD-GM-204A	PARK AND RIDE	D4-2	20+93.00	22.8 LT	GROUND MOUNT	2.5	4.0		10		1		21+00.00	24.0 LT	GROUND MOUNT	2.5	3.0	7.5			15.00			
RD-GM-204B	A.I.S.		20+93.00	22.8 LT	GROUND MOUNT								22+00.00	24.0 LT	GROUND MOUNT	4.5	3.5		15.75		31.00(2)			
RD-GM-205	DESTINATION	Specific Service	21+87.00	42.2 RT	GROUND MOUNT	7.0	6.0			42	2	2	21+50.00	52.0 RT	GROUND MOUNT	5.0	2.5		12.5		29.00(2)			
RD-GM-206	WRONG WAY	R5-1a	22+36.00	24.5 LT	GROUND MOUNT	3.0	2.0	6			1		22+50.00	24.0 LT	GROUND MOUNT	3.5	2.5	8.75			29.00(2)			
RD-GM-207	WRONG WAY	R5-1a	22+54.00	31.8 RT	GROUND MOUNT	3.0	2.0	6			1		22+50.00	52.0 RT	GROUND MOUNT	3.5	2.5	8.75			29.00			
RD-GM-208	DO NOT ENTER	R5-1	23+99.00	32.1 RT	GROUND MOUNT	3.0	3.0	9			1		24+00.00	24.0 LT	GROUND MOUNT	4.0	4.0		16		32.00(2)			
RD-GM-209	DO NOT ENTER	R5-1	24+01.00	24.6 LT	GROUND MOUNT	3.0	3.0	9			1		24+00.00	52.0 RT	GROUND MOUNT	4.0	4.0		16		32.00(2)			
RD-GM-210	ONE WAY	R6-1											24+00.00	24.0 LT	GROUND MOUNT	3.0	1.0	3			••			
RD-GM-211	ONE WAY	R6-1											24+00.00	24.0 LT	GROUND MOUNT	3.0	1.0	3			••			
TOTAL								73	30	587.5	29	16	TOTAL					89.75	173	376.75	452	•	96.00	1.00

- • SEE STEEL SIGN SUPPORT SCHEDULE
- •• SIGN PANEL TO SHARE SUPPORT WITH ANOTHER SIGN PANEL
- ••• SIGN PANEL TO BE MOUNTED ON TRAFFIC SIGNAL POLE OR LIGHT POLE
- (2) DENOTES TWO SUPPORTS REQUIRED

STEEL SIGN SUPPORT SCHEDULE

SIGN #	DESCRIPTION	DESIGNATION	PROPOSED SIZE		STEEL SIGN SUPPORT									CONCRETE FOUNDATIONS				REINFORCEMENT BARS	
			WIDTH (LF)	HEIGHT (LF)	CLEAR HEIGHT (FT)	P1 (LF)	P2 (LF)	POST TYPE	POUNDS / FT	# OF POSTS	STUB (FT)	STUB TOTAL	STEEL SIGN SUPPORT - BREAKAWAY (POUNDS)	DIAMETER	DEPTH	CU YD	CU YD TOTAL	REINF.	REINF. POUND
RB-GM-100	LODGING	Specific	12.5	5.5	8.0	13.5	15.0	W6X15	15	2	2.50	5.00	503	2.0	6.0	0.70	1.40	78	156
RB-GM-101	FOOD	Specific	14.0	5.5	8.0	13.5	15.0	W6X15	15	2	2.50	5.00	503	2.0	6.0	0.70	1.40	78	156
RB-GM-102	GAS	Specific	14.0	5.5	8.0	13.5	15.0	W6X15	15	2	2.50	5.00	503	2.0	6.0	0.70	1.40	78	156
RB-GM-113	I 55 SOUTH	Destination	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	2.0	6.0	0.70	1.40	78	156
RD-GM-200	FOOD	Specific	14.0	5.5	8.0	13.5	13.5	W6X15	15	2	2.50	5.00	480	2.0	6.0	0.70	1.40	78	156
RD-GM-201	GAS	Specific	14.0	5.5	8.0	13.5	13.5	W6X15	15	2	2.50	5.00	480	2.0	6.0	0.70	1.40	78	156
TOTAL						139.5							2468				8.4		936

FILE NAME = S:\JOL\6328--6399\6246\055\Micros\CADD Sheets\60W13-sht-sign-sched.dgn

STRAND ASSOCIATES® 1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200

USER NAME = dennisw	DESIGNED - JLB	REVISED -	
MODEL NAME = Default	DRAWN - DJW	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - BMA	REVISED -	
PLOT DATE = 12/30/2013	DATE - 12/17/13	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGN SCHEDULES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14-N	WILL	163	58
		CONTRACT NO. 60W13		
		ILLINOIS FED. AID PROJECT		