


NOTES

1. THE EXISTING LIGHT POLE IDENTIFICATION NUMBERS SHALL BE REMOVED AND NEW POLE IDENTIFICATION NUMBERS SHALL BE PROVIDED AS SHOWN ON THE PROPOSED LIGHTING PLANS AND LIGHTING CONTROLLER WIRING DIAGRAM. THIS WORK SHALL BE INCIDENTAL TO MAINTENANCE OF LIGHTING SYSTEM.
2. THE CONTRACTOR IS TO INSTALL NEW LIGHTING CONTROLLER "M" AND ASSOCIATED NEW CONNECTIONS TO EXISTING ComED SERVICE POLE AND EXISTING LIGHTING CIRCUITS PRIOR TO REMOVAL OF EXISTING CONTROLLER. REMOVAL AND REINSTALLATION SHALL OCCUR ON SAME DAY SO SYSTEM REMAINS OPERATIONAL AT ALL TIMES.
3. THE UNDERGROUND CABLES SHALL BE REMOVED AS PER STANDARD SECTION 842. THIS WORK SHALL BE INCLUDED IN THE COST OF REMOVAL OF EXISTING CONTROLLER.
4. THE UNDERGROUND CABLES SHALL BE REMOVED AS PER STANDARD SECTION 842. THIS WORK SHALL BE INCLUDED IN THE COST OF REMOVAL OF POLE FOUNDATION.
5. TEMPORARY LIGHTING UNITS SHALL NOT BE REMOVED UNIL PERMANENT LIGHTING SYSTEM IS PLACED IN APPROVED OPERATION.
6. AERIAL CABLE SHALL BE INSTALLED SUCH THAT THE MINIMUM CLEARANCE FROM GROUND IS NOT LESS THAN 20 FT AND IS A MINIMUM OF 10 FT FROM OVERHEAD UTILITY LINES.

SEE SHEET E-6 FOR MODIFICATIONS TO POLES MC7 & MC8



USER NAME - USER.	DESIGNED - RP/DJ	REVISED -
FILE NAME - D:\160\113-shc-light-03.dgn	DRAWN - RE/DJ	REVISED -
PLOT SCALE - 5/8"=1'-0"	CHECKED - MK	REVISED -
PLOT DATE - 12/17/2013	DATE - 12/17/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**EXISTING LIGHTING REMOVAL AND TEMPORARY PLAN
AT RAMP B AND US ROUTE 30**
SCALE: 1" = 50' SHEET 3 OF 8 SHEETS STA. 5+00 TO STA. 25+00

F.A.P. RTE. 575	SECTION 14-N	COUNTY WILL	TOTAL SHEETS 163	SHEET NO. 96
CONTRACT NO. 60W13				ILLINOIS FED. AID PROJECT