

**EARTHWORK SCHEDULE**

FROM STATION	TO STATION	EARTH EXCAVATION (20200100)	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) [EARTH EXCAVATION * 0.85]	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CUYD	CUYD	CUYD	CUYD
HARRISON STREET					
7811+03.60	7811+10.00	0	0	10	-10
7811+10.00	7811+18.00	0	0	22	-22
7811+18.00	7811+33.70	4	3	64	-61
7811+33.70	7811+44.50	8	7	31	-24
7811+44.50	7811+50.00	6	5	9	-4
7811+50.00	7811+70.17	16	14	56	-42
7811+70.17	7811+74.00	3	3	11	-8
BRIDGE OMISSION					
7813+08.17	7813+10.00	24	20	3	17
7813+10.00	7813+20.00	317	269	0	269
7813+20.00	7813+30.00	395	336	0	336
7813+30.00	7813+44.25	249	212	1	211
7813+44.25	7813+73.75	82	70	10	60
7813+73.75	7813+79.75	16	14	3	11
7813+79.75	7814+00.00	63	54	10	44
7814+00.00	7814+10.00	48	41	5	36
7814+10.00	7814+50.00	74	63	71	-8
TOTAL		1305	1109	306	803
ROUNDED TOTAL		1305	1110	310	805

• NOT A PAY ITEM.

FILE PATH = p:\388035-p\m\escomon\me\local\AECOM\0\Documents\01\_Americas\Transportation\62629938\_Circle\Phase\_1\000\_CAD\005\_Roadway\Sheets\60W71\_Contract\0160W71-sht-Schedule-03.dgn



D160W71-sht-Schedule-03.dgn	DESIGNED - OPS	REVISED -
USER NAME = pimsarno	DRAWN - OPS	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED - DBM	REVISED -
PLOT DATE = 2/19/2014	DATE - 02/19/14	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NONE    SHEET 3 OF 3 SHEETS    STA.    TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	23
CONTRACT NO. 60W71				
ILLINOIS FED. AID PROJECT				