

**EXISTING UTILITY STRUCTURE SCHEDULE**

STATION	OFFSET	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EXISTING VENT STRUCTURE - BASE OF VENT TO BE BURIED *	FILLING VALVE VAULTS	FILLING VALVE VAULTS (SPECIAL)	FIRE HYDRANTS TO BE REMOVED	REMOVE EXISTING VALVE AND VAULT	COMMENTS
		(EA)	(EA)	(EA)	(EA)	(EA)	(EA)	
<b>HARRISON STREET</b>								
7810+81.93	65.24 RT	1						CITY OF CHICAGO WATER MAIN STRUCTURE
7810+98.76	58.07 RT	1						CITY OF CHICAGO WATER MAIN STRUCTURE
7811+14.66	37.91 RT	1						CITY OF CHICAGO WATER VALVE VAULT
7811+19.78	41.90 RT		1					CITY OF CHICAGO WATER VENT STRUCTURE
7811+25.19	29.67 LT				1			CITY OF CHICAGO WATER VAULT TO BE FILLED (LARGE DIAMETER)
7811+29.93	8.59 RT	1						CITY OF CHICAGO ELECTRICAL MANHOLE
7811+38.74	8.42 RT	1						CITY OF CHICAGO ELECTRICAL MANHOLE
7811+66.78	95.30 RT	1						CITY OF CHICAGO WATER MAIN STRUCTURE
7811+67.48	34.71 RT						1	CITY OF CHICAGO WATER MAIN STRUCTURE
7811+72.36	59.81 RT	1						CITY OF CHICAGO WATER MAIN STRUCTURE
7811+89.65	27.02 RT					1		CITY OF CHICAGO FIRE HYDRANT
7813+57.30	22.82 RT			1				UNKNOWN WATER MAIN STRUCTURE
7813+76.48	28.05 LT				1			CITY OF CHICAGO WATER VAULT TO BE FILLED (LARGE DIAMETER)
7813+97.52	22.29 RT			1				UNKNOWN WATER MAIN STRUCTURE
7814+06.17	10.80 RT	1						CITY OF CHICAGO ELECTRICAL MANHOLE
TOTALS		8	1	2	2	1	1	

\* NOT A PAY ITEM

**WATER MAIN SCHEDULE**

UPSTREAM STATION	DOWNSTREAM STATION	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 8"	WATER MAIN REMOVAL, 8"	TRENCH BACKFILL
		FOOT	FOOT	CU YD
<b>EAST CERMAK PUMPING STATION DRIVEWAY</b>				
10+48	10+73	34		24.4
10+87	10+98		29	20.8
ROUNDED TOTAL		34	29	45.2

**NOTES:**

- ADDITIONAL TRENCH BACKFILL QUANTITY PROVIDED ON THE DRAINAGE AND UTILITY SCHEDULES FOR EXISTING AND PROPOSED DRAINAGE PIPES.

FILE PATH = p:\388035\pmt\escomon\me\local\AECOM\Documents\01\_Americas\Transportation\6269938\_Circle\Phase\_1\000\_CAD\005\_Roadway\_Sheets\60W71-Contract\0160W71-sht-Schedule-Drain-01



D160W71-sht-Schedule-Drain-01  
 USER NAME = ch1ue  
 PLOT SCALE = 100.0000' / in.  
 PLOT DATE = 2/21/2014

DESIGNED - MSC  
 DRAWN - MSC  
 CHECKED - DBM  
 DATE - 02/19/14

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DRAINAGE AND UTILITY SCHEDULES**

SCALE: NTS      SHEET 1 OF 3 SHEETS      STA.      TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	24
CONTRACT NO. 60W71				
ILLINOIS FED. AID PROJECT				