

EXISTING DRAINAGE STRUCTURE SCHEDULE

STATION	OFFSET	CATCH BASINS TO BE RECONSTRUCTED	MANHOLES TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	COMMENTS	
		EACH	EACH	EACH	EACH	EACH	EACH		
HARRISON STREET									
7811+25.00	8.73' LT		1					EX RIM EL = 596.81	PR RIM EL = 596.09
7811+33.17	24.61' RT					1			
7811+36.07	24.37' LT				1				
7811+46.87	27.29' LT						1	EX RIM EL = 596.70	PR RIM EL = 598.14
7811+52.65	11.13' RT				1				
7811+71.71	23.15' RT			1					
7813+44.53	1.95' RT			1					
7813+44.13	48.28' LT				1				
WEST CERMAK PUMPING STATION DRIVEWAY									
20+28.88	0.90' LT		1					EX RIM EL = 594.40	PR RIM EL = 594.40
EAST CERMAK PUMPING STATION DRIVEWAY									
10+54.85	3.01' LT		1					EX RIM EL = 594.78	PR RIM EL = 594.93
NE RAMP									
7+42.65	20.00' RT				1				
8+13.68	32.02' RT				1				
9+79.10	14.55' RT	1						EX RIM EL = 589.65	PR RIM EL = 589.65
TOTALS		1	3	2	5	1	1		

EXISTING DRAINAGE PIPE SCHEDULE

DRAINAGE AND UTILITY SHEET NO.	STATION	TRENCH BACKFILL	STORM SEWER REMOVAL	TELEVISION INSPECTION OF SEWER	COMBINED SEWERS TO BE CLEANED	COMBINED SEWER REMOVAL			STORM SEWERS TO BE CLEANED	
		CU YD	FOOT	FOOT	FOOT	8"	12"	60"	12"	18"
1/2	HARRISON STREET	390.6	97	308	132	48	133	57	-	-
3/4	NB I-90/94 (INCLUDES NW AND NE RAMP)	0.9	174	444	-	-	-	-	222	22
ROUNDED TOTAL		391.5	271	752	132	48	133	57	222	22

NOTES:

- ADDITIONAL TRENCH BACKFILL QUANTITY PROVIDED ON THE DRAINAGE AND UTILITY SCHEDULES FOR WATER MAIN AND PROPOSED DRAINAGE PIPES.

PROPOSED DRAINAGE PIPE UNDERDRAINS SCHEDULE

PIPE UNDERDRAINS	UPSTREAM				DOWNSTREAM				PIPE UNDERDRAINS	PIPE UNDERDRAINS
	STRUCTURE	STATION	OFFSET	INVERT ELEVATION	STRUCTURE	STATION	OFFSET	INVERT ELEVATION	6"	6"
									(SPECIAL)	
		FOOT		FOOT				FOOT		
HARRISON STREET										
PU-02	-	7813+46.25	2.73' RT	589.91	S-07	7813+85.00	2.72' RT	586.63	33	6
ROUNDED TOTAL									33	6

FILE PATH = p:\388035\pmt\escomon\me\local\AECOM\Documents\01_Americas\Transportation\6269938_Circle\Phase_1\000_CAD\005_Roadway\Sheets\60W71_Contract\160W71-sht-Schedule-Drain-02



D160W71-sht-Schedule-Drain-02
 USER NAME = ChiuA
 PLOT SCALE = 100.0000' / 1" =
 PLOT DATE = 2/17/2014

DESIGNED - AFC
 DRAWN - AFC
 CHECKED - EY
 DATE - 02/19/14

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

DRAINAGE AND UTILITY SCHEDULES

SCALE: NTS SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	25
CONTRACT NO. 60W71				
ILLINOIS FED. AID PROJECT				