




TYPICAL END TREATMENT AT SIDEWALK

Shorter plates with a single row of studs at 12" cts. may be necessary on sidewalks which are shallower than 9". See manufacturer's recommendation.



PLAN



SECTION THRU ROLLED RAIL JOINT AT SIDEWALK

SECTION THRU WELDED RAIL JOINT AT ADA RAMP

**Cost shall be included with Preformed Joint Strip Seal

Note: At East Abut. and West Abut. attach cover plate to the Ramp Pavement with 1/2 inch S.S. CTSK capscrew with concrete insert at 1'-0" cts.


SECTION THRU ROLLED RAIL JOINT

SECTION THRU WELDED RAIL JOINT

* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.

NOTES:

- The strip seal shall be made continuous and shall have a minimum thickness of 1/4". The configuration of the strip seal shall match the configuration of the Locking Edge Rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.
- The Locking Edge Rails depicted are conceptual only, except for the minimum dimensions shown. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer. Flanged edge rails will not be allowed. Locking Edge Rails may be spliced at slope discontinuities.
- The manufacturer's recommended installation methods shall be followed.
- The joint opening and deck dimensions detailed on the superstructure are based on a rolled rail expansion joint. If the Contractor elects to use the welded rail expansion joint, the opening and deck dimensions shall be modified according to the dimensions detailed on this sheet. Required modifications shall be made at no additional cost to the State.
- All steel components except expansion joint plates and attached bars shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.
- Maximum space between rail segments shall be 3/16", sealed with a suitable sealant. Joints in rails within 10 ft. of curbs shall be welded.



ROLLED EXTRUDED RAIL WELDED RAIL LOCKING EDGE RAILS

*** Back gouge not required if complete joint penetration is verified by mock-up.

LOCKING EDGE RAIL SPLICE
The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.

BILL OF MATERIAL

Item	Unit	Total
Preformed Joint Strip Seal	Foot	135



USER NAME = dunkerleyb	DESIGNED - DEV	REVISED
PLOT SCALE = N.T.S.	CHECKED - DD	REVISED
PLOT DATE = 12/17/2013	DRAWN - DEV	REVISED
	CHECKED - DD	REVISED

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

EXPANSION JOINT DETAILS STRUCTURE NO. 016-1711

SHEET NO. S-26 OF S-47 SHEETS

F.A.I. RTE. 90/94/290	SECTION 2013-036R	COUNTY COOK	TOTAL SHEETS 256	SHEET NO. 118
CONTRACT NO. 60W71			ILLINOIS FED. AID PROJECT -NUMBER-	

0161711-60W71-S26-ExpJoint