

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	BRIDGE	HIGHWAY LIGHTING
				0004 URBAN	0011 S. N. 016-1711	0021 URBAN
44000100	PAVEMENT REMOVAL	SQ YD	383	383		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	219	219		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	496	496		
44000300	CURB REMOVAL	FOOT	170	170		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	420	420		
44000600	SIDEWALK REMOVAL	SQ FT	2392	2392		
44001980	CONCRETE BARRIER REMOVAL	FOOT	118	118		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	184	184		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50157300	PROTECTIVE SHIELD	SQ YD	1128		1128	
50200100	STRUCTURE EXCAVATION	CU YD	1064		1064	
50300225	CONCRETE STRUCTURES	CU YD	335		335	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	734		734	
50300260	BRIDGE DECK GROOVING	SQ YD	1068		1068	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev.

FILE PATH: I:\12-223-WP&C\0160471-11-500.dgn



D:\60471-sht-500.dgn
 USER NAME: j.pisano
 PLOT SCALE: 2.0000 "/>

DESIGNED - OPS
 DRAWN - OPS
 CHECKED - DBM
 DATE - 12/06/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 3 OF 14 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	8
CONTRACT NO. 60W71			ILLINOIS FED. AID PROJECT	