

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	BRIDGE	HIGHWAY LIGHTING
				0004	0011	0021
				URBAN	S. N. 016-1711	URBAN
* 81603081	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND. (XLP-TYPE USE) 1 1/2" DIA. POLYETHYLENE	FOOT	150			150
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2050			2050
* 82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	3			3
* 82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	6			6
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	18			18
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	2			2
Z0004552	APPROACH SLAB REMOVAL	SQ YD	527	527		
* Z0007118	UNTREATED TIMBER LAGGING	SQ FT	458		458	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	78		78	
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	13		13	
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	59	59		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	145	145		
Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	323		323	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev.

FILE PATH: I:\13-1223-000A\06071-1-1-500.dgn



D:\6071-1-1-500.dgn
 USER NAME: pmsarno
 PLOT SCALE: 2.0000 "/>

DESIGNED - OPS
 DRAWN - OPS
 CHECKED - DBM
 DATE - 12/06/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 10 OF 14 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	15
CONTRACT NO. 60W71				

ILLINOIS FED. AID PROJECT