

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	BRIDGE	HIGHWAY LIGHTING
				0004 URBAN	0011 S. N. 016-1711	0021 URBAN
X0370185	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 12 INCH (CDOT)	FOOT	32	32		
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100		
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	1400	1400		
X4240800	DETECTABLE WARNINGS (SPECIAL)	SQ FT	17	17		
* X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	222	222		
* X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	22	22		
X5610708	WATER MAIN REMOVAL, 8"	FOOT	29	29		
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	212		212	
X6011705	PIPE DRAINS 6" (SPECIAL)	FOOT	6	6		
X6020083	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	1	1		
X6020270	MANHOLES TYPE B, 4' DIA., TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1		
X6022505	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	3	3		
X6028000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1		
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8		
X6640050	CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL)	FOOT	33		33	
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	69	69		

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM (100% STATE)



D:\GOW71\sh1-500.dgn
 USER NAME * pimsarno
 PLOT SCALE * 2.0000 ' / in.
 PLOT DATE * 12/23/2013

DESIGNED - OPS
 DRAWN - OPS
 CHECKED - DBM
 DATE - 12/05/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 14 OF 14 SHEETS STA. TO STA.

F.A.I. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	19
CONTRACT NO. GOW71				
ILLINOIS FED. AID PROJECT				

Rev.

FILE PATH : I:\13-1223-MORNING\GOW71-sh1-500.dgn