

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				0021	0021	0021	0021
				90% FEDERAL 10% STATE ROADWAY	90% FEDERAL 7.5% STATE 2.5% CITY TRAF. SIGNALS	100% CITY SAFETY (EVP)	90% FEDERAL 10% STATE INTERCONNECT
	<i>URBAN</i>						
20200100	EARTH EXCAVATION	CU YD	192	192			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	494	494			
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	229	229			
35600718	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/2"	SQ YD	386	386			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	43	43			
40600300	AGGREGATE (PRIME COAT)	TON	0.3	0.3			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	91	91			
40600027	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	63	63			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	36	36			
44000100	PAVEMENT REMOVAL	SQ YD	254	254			
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	413	413			
44003100	MEDIAN REMOVAL	SQ FT	2,138	2,138			
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	2,169	2,169			
60624600	CORRUGATED MEDIAN	SQ FT	213	213			
△ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	192	192			
△ 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			

FILE NAME: S:\FILES\...

SHT_PLAN

USER NAME: *USER*	DESIGNED - BFH	REVISED -
DRAWN - BFH	CHECKED - BA	REVISED -
PLOT SCALE: *SCALE*	DATE - 1/31/14	REVISED -
PLOT DATE: *DATE*		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
UR RTE. 6 (159TH STREET) AND IL RTE. 83 (TORRENCE AVENUE)

SCALE: N.T.S. SHEET 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	539N-1	COOK	49	3
CONTRACT NO. 60W90			ILLINOIS FED. AID PROJECT	

△ Specialty Hem Rev.