

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HSIP FUNDS			
				90% FEDERAL 10% STATE	100% CITY OF NAPERVILLE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				0021			
			TRAFFIC SIGNALS		LIGHTING		
			U.S. ROUTE 34/ IL ROUTE 59	EM. VEHICLE PREEMPTION	INTERCONNECT	U.S. ROUTE 34/ IL ROUTE 59	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	3934	2127		1807	
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	377	57			320
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1392	197			1195
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1149	1149			
81400100	HANDHOLE	EACH	8	8			
81400200	HEAVY-DUTY HANDHOLE	EACH	4	4			
81400300	DOUBLE HANDHOLE	EACH	4	4			
81603051	UNIT DUCT, 600 V, 3-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	3386				3386
81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	330				330
81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	2708				2708
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	13				13
82500365	LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 150 AMP	EACH	1				1

URBAN



USER NAME = jps	DESIGNED - BRD	REVISED -
PLOT SCALE = 48.0000' / 1in.	DRAWN - MFB	REVISED -
PLOT DATE = 1/28/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
NO SCALE	SHEET NO. 3 OF 9 SHEETS	STA.	TO STA.

F.A.P. RTE. 331	SECTION 2013-062TS	COUNTY	TOTAL SHEETS 49	SHEET NO. 5
			DUPAGE	CONTRACT NO. 60X34
ILLINOIS FED. AID PROJECT				