

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HSIP FUNDS			
				90% FEDERAL 10% STATE	100% CITY OF NAPERVILLE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				0021			
			TRAFFIC SIGNALS		LIGHTING		
			U.S. ROUTE 34/ IL ROUTE 59	EM. VEHICLE PREEMPTION	INTERCONNECT	U.S. ROUTE 34/ IL ROUTE 59	
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M. H., 15 FT. MAST ARM	EACH	7				7
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	70				70
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	7				7
84200804	REMOVAL OF POLE FOUNDATION	EACH	2				2
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1				1
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1				1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1				1
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4			4	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1	1			
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5086			5086	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1373	1373			

URBAN



USER NAME = jje
 DESIGNED - BRD
 DRAWN - MFB
 PLOT SCALE = 40.0000' / 1" = 1'
 CHECKED - JJE
 PLOT DATE = 1/30/2014
 DATE = 01/30/2014

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

NO SCALE SHEET NO. 4 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	2013-062TS		49	6
CONTRACT NO. 60X34			ILLINOIS FED. AID PROJECT	