
## SCHEDULE OF QUANTITIES


	SCHEDULE OF QUARTITIES		
	PAY ITEM	UNIT	QNTY.
SL	BBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	21
PR	OTECTIVE COAT	SQ YD	24
PC	RTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	189
DE	TECTABLE WARNINGS	SQ FT	34
CC	MBINATION CURB AND GUTTER REMOVAL	F00T	13
SI	DEWALK REMOVAL	SQ FT	76
CL	ASS D PATCHES, TYPE I, 12 INCH	SQ YD	11
CC	MBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	13
EN	IGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
-	IANGEABLE MESSAGE SIGN	CAL MO	1
	GN PANEL - TYPE 1	SQ FT	30
_	GN PANEL - TYPE 2	SQ FT	68
_	IERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	13
-	VEMENT MARKING REMOVAL	SQ FT	13
	RVICE INSTALLATION - POLE MOUNTED	EACH	1
-	IDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	629
	IDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA,	FOOT	5
_	IDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	100
_	IDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	476
_	NDHOLE	EACH	4
-	AVY-DUTY HANDHOLE	EACH	2
-	DUBLE HANDHOLE	EACH	1
	ANSCEIVER - FIBER OPTIC  ECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	234
-	ECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	817
-	ECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3899
-	ECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	219
_	ECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1784
	ECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	46
_	ECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	760
-	EEL MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1
_	TEEL MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	2
_	EEL MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1
ST	EEL MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1
ST	EEL MAST ARM ASSEMBLY AND POLE 62 FT.	EACH	1
CC	NCRETE FOUNDATION, TYPE A	FOOT	4
CC	NCRETE FOUNDATION, TYPE C	FOOT	4
CC	NCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	51
CC	NCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15
CC	NCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	F00T	21
SI	GNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	15
SI	GNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1
SI	GNAL HEAD, LED, 2-FACE,3-SECTION, BRACKET MOUNTED	EACH	1
SI	GNAL HEAD, LED, 2-FACE,1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1
TR	RAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	16
IN	DUCTIVE LOOP DETECTOR	EACH	7
DE	TECTOR LOOP, TYPE I	FOOT	818
LI	GHT DETECTOR	EACH	3
LI	GHT DETECTOR AMPLIFIER	EACH	1
TE	MPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
RE	LOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	2
	LOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	2
_	LOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1750
_	MOVE ELECTRIC CABLE FROM CONDUIT MOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	FOOT EACH	1358
_	MOVE EXISTING HANDHOLE	EACH	8
$\vdash$	MOVE EXISTING DOUBLE HANDHOLE	EACH	1
_	MOVE EXISTING CONCRETE FOUNDATION	EACH	11
$\vdash$	MERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	566
_	INDUIT SPLICE  JLL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH EACH	1
_	VINTERRUPTABLE POWER SUPPLY SPECIAL	EACH	1
-	MPORARY TRAFFIC SIGNAL TIMING	EACH	1
TR	RAINEES	HOURS	170
	* 100% COST TO THE VILLAGE OF BENSENVILLE		

- \* 100% COST TO THE VILLAGE OF BENSENVILLE
- \*\* SUPER P CABINET


## PROPOSED CONTROLLER SEQUENCE



## PROPOSED EMERGENCY VEHICLE PREEMPTION SEQUENCE



PROPOSED EMERGENCY VEHICLE PREEMPTORS							
EMERGENCY VEHICLE PREEMPTOR	3	4	5				
MOVEMENT	=	ī					



CIVITECH

USER NAME = jrt	DESIGNED	-	BRD	REVISED	-
	DRAWN	-	JRT	REVISED	-
PLOT SCALE = 40.0000 ' / in.	CHECKED	-	JJE	REVISED	-
PLOT DATE = 1/30/2014	DATE	-	01/30/2014	REVISED	-

	PHASE DESIGNATION DIAGRAM, EMERGENCY VEHICLE PREEMPTION SEQUENCE & SCHEDULE OF QUANTITIES IL ROUTE 83 (KINGERY HWY.) AT GROVE AVENUE /SHERWOOD DRIVE									
NOT TO SCALE	SHEET NO.	1 OF	1 SHEETS	STA.	TO STA.					

F.A.P. RTE.	SECT	ION	COUNTY	TOTAL SHEETS	SHE	
344	2013-0	63TS	DUPAGE	68	3	
		CONTRAC	Γ NO. 6	0X3		
		D PROJECT				

TS# 595