

CONSTRUCTION CODE

HSIP FUNDS

90% FEDERAL 5% STATE 5% ADDISON/TWIP	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% WOOD DALE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% CENTERPOINT	100% BENSENVILLE	90% FEDERAL 10% STATE
--	---	---	---	---	---------------------	--------------------------

URBAN

0021

TRAFFIC SIGNALS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS						
				IL ROUTE 83 AT THIRD AVENUE/OAK MEADOWS DRIVE	IL ROUTE 83 AT GROVE AVENUE/SHERWOOD DRIVE	IL ROUTE 83 AT HILLSIDE DRIVE	IL ROUTE 83 AT FOSTER AVENUE	IL ROUTE 83 AT MARK STREET	EM. VEHICLE PREEMPTION	INTERCONNECT
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	34084	1431	1358	1641		1171		28483
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5	1	1	1	1	1		
89502380	REMOVE EXISTING HANDHOLE	EACH	32	9	8	5	5	5		
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	5	1	1	1	1	1		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	44	11	11	11		11		
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	3152						3152	
X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1				1			
X8100105	CONDUIT SPLICE	EACH	4	1	1			2		
** X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2		1		1			
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	5	1	1	1	1	1		
** X8630104	CONTROLLER CABINET, TYPE IV, SPECIAL	EACH	3	1		1		1		

** SUPER P CABINET



USER NAME - JJK	DESIGNED - BRD	REVISED -
PLOT SCALE - 40,0000 1/16"	DRAWN - JRT	REVISED -
PLOT DATE - 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL SUMMARY OF QUANTITIES

IL ROUTE 83
THIRD AVENUE /OAK MEADOWS DRIVE TO MARK STREET

NO SCALE SHEET NO. 9 OF 10 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	2013-0637S	DUPAGE	68	11
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60X35	