

PATCHING SCHEDULE

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
422+70	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
422+58	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
422+20	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
421+81	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
421+40	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
420+92	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
420+57	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
420+17	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
419+78	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
419+35	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
418+98	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
418+59	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
418+23	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
418+14	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
417+81	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
417+37	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
416+98	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
416+54	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
416+19	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
415+79	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
415+38	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
415+00	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
414+56	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
414+19	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
413+78	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
413+38	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
412+19	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
411+79	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
411+37	SB	Entrance	6	19	0.0	12.7	0.0	0.0	36	69.0	0	0.0
410+96	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
410+60	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
410+17	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
409+33	SB	Entrance	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
SHEET TOTALS					0.0	354.0	0.0	0.0	932	1989.0	0.0	0.0

PATCHING SCHEDULE

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
407+80	SB	Bypass	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
407+50	SB	Bypass	24	16	0.0	0.0	0.0	42.7	28	96.0	24	42.7
406+99	SB	Bypass	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
SHEET TOTALS					0.0	106.7	0.0	42.7	308	696.0	24.0	42.7

PATCHING SCHEDULE

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
408+56	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
408+23	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
407+81	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
407+44	SB	Scale	16	16	0.0	0.0	0.0	28.4	28	80.0	16	28.4
406+99	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
406+62	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
406+07	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
405+64	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
405+29	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
404+86	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
404+50	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
404+05	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
403+61	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
403+25	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
402+82	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
402+51	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
402+38	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
402+10	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
401+98	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
401+70	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
401+28	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
400+87	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
400+44	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
400+08	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
399+65	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
399+27	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
398+81	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
398+43	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
398+00	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
397+61	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
396+82	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
396+46	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
396+01	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
397+81	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
398+75	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
386+59	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
386+20	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
385+80	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
385+41	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
385+00	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
384+64	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
383+79	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
382+60	SB	Scale	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
SHEET TOTALS					0.0	448.0	0.0	28.4	1204	2600.0	16.0	28.4

FINAL TOTALS

Lane	PATCH AREA				DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
	TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
Entrance	0.0	354.0	0.0	0.0	932.0	1989.0	0.0	0.0
Bypass	0.0	21.3	0.0	42.7	84.0	216.0	24.0	42.7
Scale	0.0	448.0	0.0	28.4	1204.0	2600.0	16.0	28.4
FINAL TOTAL	0.0	823.3	0.0	71.1	2220.0	3616.0	40.0	71.1

FILE NAME =	USER NAME = hardnettbr	DESIGNED -	REVISED -
c:\pw\work\p\pidot\hardnettbr\d0370739\0	12514-sh-t-plan.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 126.5724' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/10/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(99-1TWS-2)PP-1	WILL	14	4
CONTRACT NO. 60X54				
ILLINOIS FED. AID PROJECT				