

**PATCHING SCHEDULE  
FOR CLASS B PATCHES**

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS 1 1/2" 44201299 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 1" 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I	TYPE II	TYPE III	TYPE IV				
					(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)				
1090+39	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1088+50	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1087+83	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1088+25	SB	BYPASS	27	14	0.0	0.0	0.0	42.0	24	96.0	27	42.0
1087+54	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1087+37	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1087+30	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1086+50	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1086+72	SB	BYPASS	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1086+39	SB	BYPASS	9	14	0.0	14.0	0.0	0.0	24	60.0	0	0.0
<b>PASSING LANE SUBTOTALS</b>					0.0 (sq. yd)	88.7 (sq. yd)	0.0 (sq. yd)	42.0 (sq. yd)	240.0 (Each)	588.0 (ft)	27.0 (Each)	42.0 (sq. yd)

FILE NAME =	USER NAME = pyzranowskirb	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE BYPASS LANE</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\pyzranowskirb\0370428	ND112614-sht-plan.dgn	DRAWN -	REVISED -		57	199-2TWSJPP	WILL	18	5				
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		<b>CONTRACT NO. 60X55</b>				ILLINOIS FED. AID PROJECT				
	PLOT DATE = 2/3/2014	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.			