## INDEX OF SHEETS

- COVER SHEET
- INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
- SUMMARY OF QUANTITIES
- STAGING TYPICALS FOR SN 037-0003 & 037-0004
- TRAFFIC CONTROL PLAN STAGE I FOR SN 037-0003 & 037-0004
- 10 14 TRAFFIC CONTROL PLAN STAGE II FOR SN 037-0003 & 037-0004
- 15 17 TYPICAL PAVEMENT MARKINGS (DIST STD 41.1)
- PAINTING DETAILS (DIST STD 44.1)
- INFORMATIONAL WARNING SIGN (FOR NARROW TRAVEL LANES) (DIST STD 39.2) 19
- 20 PLAN AND ELEVATION SN 037-0003 & 037-0004
- CONCRETE REMOVAL DETAILS SN 037-0003 & 037-0004 21
- 22 23 SUPERSTRUCTURE DETAILS SN 037-0003 & 037-0004
- 24 JOINT DETAILS SN 037-0003 & 037-0004
- 25 BAR SPLICER ASSEMBLY DETAILS SN 037-0003 & 037-0004
- 26 27 PIER REPAIR DETAILS

## STATE STANDARDS

- 000001 06 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- DECIMAL EQUIVALENTS OF AN INCH AND FOOT
- 701006 05 OFF ROAD OPERATIONS, 2L, 2W, 15'(4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
- 701101 04 OFF ROAD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
- 701201 04 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
- 701301 04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701400 07 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701401 08 LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701402 09 LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
- 701426 06 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS ≥ 45 MPH
- 701901 03 TRAFFIC CONTROL DEVICES
- 704001 07 TEMPORARY CONCRETE BARRIER
- 720011 01 METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
- 728001 01 TELESCOPING STEEL SIGN SUPPORT
- 729001 01 APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

## **GENERAL NOTES**

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

(Type name & phone number of JULIE companies from attached utility form.)

Electric:

MIDAMERICAN ENERGY ATTN: JASON TERRY (309) 793-3649 2811 5TH AVENUE **ROCK ISLAND, IL 61201** 

MIDAMERICAN ENERGY COMPANY ATTN: ROD HAWK (309) 793-3760 2811 5TH AVENUE **ROCK ISLAND, IL 61201** 

Telephone:

GENESEO TELEPHONE CO. ATTN: ROGER GRANELL (309) 944-8025 111 EAST 1ST STREET GENESEO, IL 61254

ATTN: DAVID CREEN (309) 757-4707 2800 7TH STREET

IDOT is not a member of JULIE. If you are near any overhead lighting, intersection lighting or traffic signals, contact the IDOT Traffic Office at 815/284-5469 at least 48 hours prior to work.

Hazards behind Temporary Concrete Barrier Wall

No materials, equipment, vehicles or other hazards shall be within 3'-6" of the temporary concrete barrier wall, measured from the closest point of the barrier wall perpendicular to the hazard. Equipment that is actively working with 3'-6" of the barrier wall may be allowed for a short duration, if approved by the engineer, required for the work activity, and there is not another method to complete the work.

FILE NAME :	USER NAME : dosadd	DESIGNED	-		REVISED			
01/88/00as/Henry/64E94 Repoirs SN 937-0	003 and SN 037-0004\CADD\0205509-sht-cover	4 <del>8</del> 88₩N	~		REVISED	*		
	PLOF SCALE * 100.0000 '/ in.	CHECKED	-		PEVISED			
Default	PLOT DATE + Man Jan 86 07:45:41 2014	DATE	-		REVISED			

STATI	STATE OF ILLINOIS		
DEPARTMENT	OF	TRANSPORTATION	

-	INDEX OF SHEETS, STATE STANDARDS &		SECTION	COUNTY	TOTAL	SHEET NO.
1	GENERAL NOTES	74/280	(37-1HBR)M	HENRY	27	2
1	GLIVEIAE NOIES			CONTRACT	NO. 6	34E94
Ì	SCALE: SHEET OF SHEETS STA TO STA	ILLINOIS FED. AID PROJECT				