

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE												
				URBAN	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (STATE/ CITY)	80/20 (FED/CITY)	100% (STATE)	100% (CITY OF PEORIA)	100% (STATE)
				ROADWAY	SN 072-0146	SN 072-7004	SIGNALS AT IL 6 RAMP	LIGHTING	SIGNING	MULTI-USE PATH	SIDEWALK	SIGNALS VAN WINKLE WAY	WATER MAIN	WATER MAIN	MOWING	TRAINEES
				0003	0013	0040	0021	0021	0021	0028	0021	0021	0043	0043	0003	0042
* 82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1						1							
* 83060450	LIGHT POLE, GALVANIZED STEEL, 45 FT. M.H., 15 FT. MAST ARM	EACH	34						34							
* 83060550	LIGHT POLE, GALVANIZED STEEL, 50 FT. M.H., 15 FT. MAST ARM	EACH	40						40							
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	511						511							
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	34						34							
* <del>83800505</del>	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	160						160							
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	1						1							
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	11						11							
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	12						12							
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1						1							
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1						1							
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1						1							
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3390						3390							
* 87200400	SPAN WIRE	FOOT	360						360							

\* SPECIALTY ITEM

REV. 4-11-14

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE												
				URBAN	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (STATE/ CITY)	80/20 (FED/CITY)	100% (STATE)	100% (CITY OF PEORIA)	100% (STATE)
				ROADWAY	SN 072-0146	SN 072-7004	SIGNALS AT IL 6 RAMP	LIGHTING	SIGNING	MULTI-USE PATH	SIDEWALK	SIGNALS VAN WINKLE WAY	WATER MAIN	WATER MAIN	MOWING	TRAINEES
				0003	0013	0040	0021	0021	0021	0028	0021	0043	0043	0003	0042	
X6024240	INLETS, SPECIAL	EACH	1	1												
X6024502	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	7	7												
X6061902	CONCRETE MEDIAN, TYPE SM (SPECIAL)	SQ FT	500	500												
X6062700	CONCRETE GUTTER, TYPE A (SPECIAL)	FOOT	41	41												
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24												
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1												
X7010410	SPEED DISPLAY TRAILER	CAL MO	12	12												
* X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1	1												
* X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	385	385												
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	9479	9479												
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	2005	2005												
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	3841	3841												
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	973	973												
* X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	457	457												

\* SPECIALTY ITEM

FILE NAME :	USER NAME : eub-sygs	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALLEN ROAD IMPROVEMENTS SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
st:\gen\draft\st\dplns\equad3\allen rd\al sheet revisions\0408683-shr-500.dgn	DRAWN -	REVISED -	6584			1051 (72-7HB)BY	PEORIA	487	32	
PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -	6585			CONTRACT NO. 68683				
Default	PLOT DATE = 1/31/2014 1:52:12 PM	DATE -	REVISED -			SCALE:	SHEET OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	

REV. 4-11-14