

STEEL POST REMOVAL				
LOCATION			EACH	REMARKS
505+50.00	5.70'	LT	1	ROCK ISLAND TRAIL
505+50.00	0.37'	LT	1	ROCK ISLAND TRAIL
505+50.00	4.95'	RT	1	ROCK ISLAND TRAIL
506+75.00	5.09'	RT	1	ROCK ISLAND TRAIL
506+75.00	0.17'	LT	1	ROCK ISLAND TRAIL
506+75.00	5.43'	LT	1	ROCK ISLAND TRAIL
TOTAL			6	ROUND TO 6

PIPE DRAIN REMOVAL				
LOCATION			FOOT	REMARKS
59+94.98	28.9'	LT	20.00	
TOTAL			20.0	ROUND TO 20

CONCRETE MEDIAN, TYPE SM (SPECIAL)				
LOCATION			SQ FT	REMARKS
60+59.59	TO	61+43.03	500.00	ALLEN RD
TOTAL			500.0	ROUND TO 500

CONCRETE GUTTER, TYPE A (SPECIAL)				
LOCATION			FOOT	REMARKS
97+22.32	TO	97+63.30	41.00	NORTH END ALLEN RD
TOTAL			41.0	ROUND TO 41

ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)				
LOCATION			CAL MO	REMARKS
ENTIRE PROJECT			24.0	
TOTAL			24	ROUND TO 24

VEHICLE CONTROL BOLLARDS				
LOCATION			EACH	REMARKS
120+14.73	27.53'	RT	1	ALTA LANE
TOTAL			1	ROUND TO 1

GUARDRAIL AGGREGATE EROSION CONTROL				
LOCATION			TON	REMARKS
59+97.90, 35.6'	TO	61+24.92, 37.2'	21.17	ALLEN ROAD
115+83.51, 20.3'	TO	118+05.58, 43.8'	43.28	ALTA LANE
TOTAL			64.4	ROUND TO 65

APPROACH SLAB REMOVAL				
LOCATION			SQ YD	REMARKS
56+19.36	TO	57+44.69	835.56	S OF SN 072-0146
59+59.66	TO	60+85.27	836.55	N OF SN 072-0146
TOTAL			1672.1	ROUND TO 1673

BUILDING REMOVAL NO. 1				
LOCATION			L SUM	REMARKS
82+37.27		RT	1	
TOTAL			1	ROUND TO 1

BUILDING REMOVAL NO. 2				
LOCATION			L SUM	REMARKS
83+59.06		RT	1	
TOTAL			1	ROUND TO 1

BUILDING REMOVAL NO. 3				
LOCATION			L SUM	REMARKS
89+74.98		LT	1	
TOTAL			1	ROUND TO 1

FENCE REMOVAL					
LOCATION				FOOT	REMARKS
45+39.91	TO	50+42.37	LT	502.47	ALLEN RD
55+97.52	TO	57+19.06	RT	139.21	ALLEN RD
59+85.54	TO	60+96.26	RT	129.61	ALLEN RD
66+00.00	TO	71+90.71	RT	590.72	ALLEN RD
89+86.53	TO	96+13.33	LT	748.99	ALLEN RD
92+23.63			LT	37.97	ALLEN RD
120+99.91	TO	121+97.92	LT	98.02	ALTA LN
TOTAL				2247.0	ROUND TO 2247

MATERIAL TRANSFER DEVICE			
LOCATION		TON	REMARKS
ENTIRE PROJECT		96.9	LEVELING BINDER, IL-4.75
ENTIRE PROJECT		348.5	BINDER, IL-12.5
ENTIRE PROJECT		168.6	SURFACE COURSE, N70
ENTIRE PROJECT		76.4	SURFACE COURSE, N50
TOTAL		690.3	ROUND TO 691

TIMBER RETAINING WALL REMOVAL					
LOCATION				FOOT	REMARKS
82+81.19	TO	83+10.25	RT	52.54	
89+53.94	TO	89+65.17	LT	38.48	
TOTAL				91.0	ROUND TO 91

LOCATION	EARTH EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
ALLEN ROAD STA. 45+50.00 TO STA. 98+00.00	32186.38	24139.78	36697.83	-12558.05
RAMP B STA. 19+70.59 TO STA. 23+49.16	309.03	231.77	204.08	27.69
ALTA LANE STA. 112+85.260 TO STA. 121+00.00	1278.88	959.16	4511.92	-3552.77
BROMPTON COURT STA. 42+04.20 TO STA. 43+27.61	43.34	32.51	402.52	-370.01
ROCK ISLAND TRAIL STA. 504+00.00 TO STA. 508+50.00	296.70	222.53	41.29	181.24
ILLINOIS 6 STA. 926+44.00 TO STA. 931+42.00	158.50	118.87	47.38	71.49
PRE-STAGE ALLEN RD STA. 74+07.00 TO STA. 84+87.00	631.30	473.48	358.70	114.78
STAGE I TEMP ACCESS RD STA. 91+45.00 TO STA. 96+48.00	1027.50	770.63	1832.20	-1061.58
ADJUSTMENT DUE TO STAGING*	524.40	393.30	-580.50	973.80
* ADJUSTMENTS ARE REQUIRED BECAUSE THE PROPOSED CROSS SECTIONS DO NOT TAKE INTO ACCOUNT THE EARTHWORK IN THE STAGING CROSS SECTIONS.				
TOTAL	36456.02	27342.01	43515.41	-16173.39

EARTHWORK SUMMARY		
EARTH EXCAVATION	36455	CU YD
FURNISHED EXCAVATION	16170	CU YD

FILE NAME = S:\GEN\DRIFT\STD&PLNS\SQUAD3\Allen Rd	USER NAME = aubreygs	DESIGNED -	REVISED -
Final Sheet Revisions\Revised Sheets.dgn		DRAWN -	REVISED -
PLOT SCALE = 20.0000' / in.		CHECKED -	REVISED -
Default	PLOT DATE = 1/31/2014 1:46:23 PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ALLEN ROAD IMPROVEMENTS
SCHEDULE OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6584	105: (72-7HB)BY	PEORIA	487	52
6585			CONTRACT NO. 68683	
ILLINOIS FED. AID PROJECT				