

				CONSTRUCTION CODE												
			URBAN	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (FED/ STATE)	80/20 (STATE/ CITY)	80/20 (FED/CITY)	100% (STATE)	100% (CITY OF PEORIA)	100% (STATE)	
				ROADWAY	SN 072-0146	SN 072-7004	SIGNALS AT IL 6 RAMP	LIGHTING	SIGNING	MULTI-USE PATH	SIDEWALK	SIGNALS VAN WINKLE WAY	WATER MAIN	WATER MAIN	MOWING	TRAINEES
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0003	0013	0040	0021	0021	0021	0028	0021	0021	0043	0043	0003	0042
* 81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., PVC	FOOT	175					175								
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	591				326	265								
* 81300420	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 6"	EACH	1					1								
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	5				2	3								
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	24				16	1				7				
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1									
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	345					345								
* 81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	14,000					14,000								
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	848					848								
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	24155				9152	14200				803				
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	547					547								
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	33					33								
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	45					45								
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	4					4								

\* SPECIALTY ITEM

FILE NAME =	USER NAME = eubreyga	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ALLEN ROAD IMPROVEMENTS SUMMARY OF QUANTITIES</b>				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\\ngm\draft\std\pina\quad3\allen rd\sheet revisions\0468683-shs-508.dgn	DRAWN -	REVISED -	6584						105; (TZ-7HB)BY	PEORIA	487	25	
PLOT SCALE = 20,0000' / 1"	CHECKED -	REVISED -	6585						CONTRACT NO. 68683				
Default	PLOT DATE = 1/31/2014 1:52:11 PM	DATE -	REVISED -						SCALE:	SHEET OF SHEETS	STA. TO STA.	[ILLINOIS] FED. AID PROJECT	