

				CONSTRUCTION CODE													
			URBAN	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (STATE/CITY)	80/20 (FED/CITY)	100% (STATE)	100% (CITY OF PEORIA)	100% (STATE)	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SN 072-0146	SN 072-7004	SIGNALS AT ILL 6 RAMP	LIGHTING	SIGNING	MULTI-USE PATH	SIDEWALK	SIGNALS VAN WINKLE WAY	WATER MAIN	WATER MAIN	MOWING	TRAINEES	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9				9										
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7.0				7.0										
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	54				24					30					
* 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	42				42										
* 87900200	DRILL EXISTING HANDHOLE	EACH	18				6	5				7					
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	12				10					2					
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7				7										
* 88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2				2										
* 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2				2										
* 88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	25				23					2					
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	31				21					10					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	3249				1961					1288					
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3	3													

* SPECIALTY ITEM

FILE NAME =	USER NAME = aubrags	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALLEN ROAD IMPROVEMENTS SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
W:\gen\draft\std\pins\sq\ed\allen rd\final sheet revisions\0460583-sht-500.dgn	PLOT SCALE = 20,0000 1/4 in.	CHECKED -	REVISED -			6584	105; 172-7MBBY	PEORIA	487	28	
Default	PLOT DATE = 1/21/2014 1:52:12 PM	DATE -	REVISED -			6585					CONTRACT NO. 68683
						SCALE:	SHEET OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		