

TREE REMOVAL ACRES	
LOCATION	ACRES
JOBSITE	1.5
TOTAL	1.5

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

HEAVY DUTY EROSION CONTROL BLANKET	
LOCATION	SQ YD
JOBSITE	445
TOTAL	445

TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

STONE DUMPED RIPRAP, CLASS B4	
LOCATION	TON
JOBSITE	1000
TOTAL	1000

REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	FOOT
JOBSITE	50
TOTAL	50

NO BEDDING MATERIAL AND FABRIC
SHALL BE REQUIRED UNDER THE
PROPOSED RIPRAP