

COMMITMENTS

No Commitments have been made for this project.

GENERAL NOTES

Cleaning and Painting shall be as specified in the Special Provisions for " Cleaning and Painting Existing Structural Steel" All beams, brackets and all other structural steel shall be cleaned per Near White Blast Cleaning SSPC-SP10 according to the following schedule:

Bridge Locations 1 & 2. Shall include all of span 1 plus 5 feet into span 2. Also included shall be the expansion joint area out 5 feet at the East Abutment. Paint System 1 - OZ/E/U for Bare Steel shall be used with the final finish coat for the Fascia Shall Blue (Munsel No. 10B 3/6) for the underside shall be Light Grey (Munsel No. 5B 7/1)

All Metalizing shall be as specified in the Special Provisions for " Field Thermal Spraying Metalizing" All beams,brackets and all other structural steel shall be cleaned per Near White Blast cleaning SSPC-SP10 according to the following schedule:

Bridge Locations 3 - 8. All beams, brackets and all other structural steel within 5 feet (as measured along the centerline of the bearing) either side of the deck joints.

Bridge Locations 3 - 6. All Fascia and underside beams shall be Interstate Green (Munsel No. 7.5G 4/8)
 Bridge Locations 7 & 8. All Fascia and Underside beams shall be Blue (Munsel No. 10B 3/6)

All Top Coat and Sealer shall be from the approved list from table one (1) of the Special Provisios.

AIR MONITORS - None for this Project.

QP1 & QP2 Required for this Project.

FILE NAME =	USER NAME = aubreys	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS AND GENERAL NOTES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\users\aubreys\desktop\68b49\68b49	2014 Metalizing.dgn	DRAWN -	REVISED -					VAR	D4 Bridge Metalizing 2014	Various	23	5
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				
	PLOT DATE = 2/14/2014	DATE -	REVISED -		CONTRACT NO. 68B49							