

MS30L101 02 03 07A0L101 07C0L101 07C0L102

SUMMARY OF QUANTITIES

MCDONOUGH COUNTY

CODE	ITEM DESCRIPTION	UNIT	TOTAL QTY.	MCDONOUGH COUNTY					
				CONST. TYPE CODE 0021 (SAFETY FUNDS) 90% FED 10% STATE URBAN 1 LOCATION	CONST. TYPE CODE 0021 (SAFETY FUNDS) 90% FED 5% STATE 5% CITY (MACOMB) URBAN 6 LOCATIONS	CONST. TYPE CODE 0021 (SAFETY FUNDS) 90% FED 10% CITY (MACOMB) URBAN 1 LOCATION	CONST. TYPE CODE 0021 (STATE FUNDS) 100% STATE URBAN 1 LOCATION INTERCONNECT	CONST. TYPE CODE 0021 (STATE FUNDS) 90% STATE 10% CITY (MACOMB) URBAN 9 LOCATIONS	CONST. TYPE CODE 0021 (STATE FUNDS) 80% STATE 20% CITY (MACOMB) URBAN 1 LOCATION
67100100	MOBILIZATION	L SUM	1.0	0.20	0.56			0.24	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0	0.20	0.56			0.24	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.20	0.56			0.24	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	105.0	10.0	75.0	20.0			
85700310	RAILROAD, FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1.0	1.0					
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3994.0				3994.0		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	213.0		213.0				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4032.0		2875.0	1157.0			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	544.0		544.0				
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	51.0				4.0	47.0	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	26.0		21.0	2.0	3.0		
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	17.0	2.0	15.0				
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	24.0	2.0	22.0				
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5.0				1.0	4.0	
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	13.0				5.0	8.0	

* SPECIALTY ITEM

FILE NAME : C:\Users\aubreyga\Desktop\68861 files\68861 - Macomb FYA Project (Final 1-21-14).dgn	USER NAME : aubreyga	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 310	SECTION D4 FLASHING YELLOW ARROWS 2013	COUNTY MCDONOUGH	TOTAL SHEETS 24	SHEET NO. 3		
PLOT SCALE : 38.0988 1/ in.	CHECKED - _____	REVISED - _____	SCALE: _____			STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT CONTRACT NO. 68861					
PLOT DATE : 1/31/2014	DATE - _____	REVISED - _____										