



CONSTRUCTION CODE

HPR, TURN LANE AND BICYCLE LANE ON ARCHER
ADD'L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMPS	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	100% CITY	100% CITY	100% CITY
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	80% FED 20% CITY	100% CITY	100% CITY	100% CITY	
				0004	0040	0021	0021	0021	0021	0021	0004	0021	0004	0004	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	10864.0	10302.0							562.0				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	178994.0	167894.0							11100.0				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	57082.0	55824.0							1258.0				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	9188.0	8356.0							832.0				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	7678.0	6298.0							1380.0				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3248.0	3148.0							100.0				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21349.0	21056.0							293.0				
* 72000300	SIGN PANEL - TYPE 3	SQ FT	481.0	481.0											
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3362.0	3362.0											
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1256.0	1116.0							140.0				
* 73400100	CONCRETE FOUNDATIONS	CU YD	4.0	4.0											
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	4.0	4.0											
* 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4.0	4.0											
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	80386.0	76864.0							3094.0			428.0	

FILE NAME :	USER NAME : sparkage	DESIGNED - AWM	REVISED -
o:\pwork\sparkage\0373645\067898-eh1-800.dgn		DRAWN - TJD	REVISED -
PLOT SCALE * 100.0000 / in.		CHECKED - AWM	REVISED -
Default		DATE - 12/04/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
SUMMARY OF QUANTITIES

SCALE: N/A SHEET 13 OF 24 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21W-3, TS-1, RS-71	SANGAMON	679	16
CONTRACT NO. 72890			ILLINOIS FED. AID PROJECT	

* SPECIALTY ITEM

REV. 4-15-14