



CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMPS	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	HPR, TURN LANE AND BICYCLE LANE ON ARCHER	ADD'L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	80% FED 20% CITY	100% CITY	100% CITY	100% CITY	
				0004	0040	0021	0021	0021	0021	0021	0004	0021	0004	0004	
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7998.0				7998.0								
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	6.0			2.0	3.0	1.0							
* 89502380	REMOVE EXISTING HANDHOLE	EACH	30.0			10.0	18.0	2.0							
* 89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	6.0			2.0	3.0	1.0							
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	50.0			18.0	25.0	7.0							
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	3.0	1.0							2.0				
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	3872.0		3872.0										
X0324752	STORM SEWER TO BE FILLED	CU YD	8.0	8.0											
X0326820	INLETS, SPECIAL, TYPE E, 4' X 4'	EACH	19.0	15.0							4.0				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	94172.0	92775.0							1129.0		268.0		
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	436.0			436.0									
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	8.0	5.0							3.0				
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	9.0	3.0							6.0				



FILE NAME : d:\p\work\p\p\dot\sparksg\00373645\0672890-sh1-500.dgn	USER NAME : sparksg	DESIGNED - AWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU ROUTE 8012 (WABASH AVE) SUMMARY OF QUANTITIES			F.A.U. RTE. 8012	SECTION 21(W-3, TS-1, RS-7)	COUNTY SANGAMON	TOTAL SHEETS 679	SHEET NO. 24
PLOT SCALE : 100.0000' / 1"	CHECKED - AWM	REVISED -	SCALE: N/A		SHEET 21 OF 24 SHEETS STA. TO STA.			CONTRACT NO. 72890				
PLOT DATE : Feb-04-2014 04:00:48PM	DATE - 12/04/2013	REVISED -	ILLINOIS FED. AID PROJECT									
* SPECIALTY ITEM												

△ REV. 4-15-14