

PAVEMENT SCHEDULE

STATION TO STATION	31100700	35501312	35501318	35650200	BASE COURSE WIDENING, 8 1/2"	40600200	40600300	406000837	40603085	40603540			
	SUBBASE GRANULAR MATERIAL, TYPE A 8"	HOT-MIX ASPHALT BASE COURSE, 7"	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	BASE COURSE WIDENING, 7"		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70			
	SO YD					TON							
MAINLINE WABASH AVENUE													
WABASH AVE (FAU 8012)													
340+00.00	357+40.94	5,941		5,573		5.7	30	998		977			
357+40.94	361+37.69	2,246		80		1,713	5.1	27		733			
361+37.69	366+19.35	1,938		1,745			3.6	19		536			
366+19.35	367+61.39	554				435	1.7	9		242			
367+61.39	382+60.23	5,539		4,183			7.8	41		1,114			
382+60.23	383+91.15	644				513	1.8	9		243			
383+91.15	389+15.49	2,689		2,420		69	3.9	21		575			
389+15.49	393+05.74	3,568		2,430		684	4.8	25		640			
393+05.74	408+01.83	6,175		5,592			9.2	48		1,097			
408+01.83	409+71.52	803		444		275	1.3	7		216			
409+71.52	414+99.27	1,646		1,445			2.7	15		396			
414+99.27	417+20.62	665		292		246	1.7	9		175			
417+20.62	424+95.08	2,827		2,449			4.5	23		492			
424+95.08	427+48.98	1,848		1,681			2.1	11		249			
427+48.98	431+88.53	2,519		2,199			3.2	17		487			
431+88.53	433+43.53	497		237		168	1.1	6		132			
433+43.53	436+70.35	1,114		883			2.0	11		266			
436+70.35	440+46.20	1,834					4.1	22		1,134			
440+46.20	451+32.10	4,095		3,565			6.5	34		1,061			
451+32.10	455+21.44	3,173		1,911		715	4.5	24		371			
455+21.44	463+23.01	2,737		2,173			4.5	24		498			
463+23.01	466+38.15	1,188		440		460	2.6	14		376			
466+38.15	482+20.69	4,365		3,449			9.0	47		1,349			
482+20.69	485+54.30	540					4.2	22		61			
485+54.30	492+79.37						4.2	22		620			
RAMP C													
11+11.46	15+31.46	544		463			1.1	6		66			
RAMP A													
13+36.88	18+38.48	938		726			1.4	7		76			
BUNKER HILL RD													
1+37.00	8+02.44	3,082		2,661			2.0	11		297			
ASH GROVE RD													
11+93.41	12+42.18	5		5			0.2	1		16			
ARCHER ELEVATOR RD													
11+42.19	14+66.85	1,749		1,514			1.2	6		169			
14+66.85	18+03.15	340		280			0.8	4		37			
MERCANTILE DR													
4+20.48	5+23.29						0.4	2		54			
5+23.29	6+61.08	641		413		111	1.2	6		182			
6+61.08	8+56.86	67					1.0	5		146			
STADIUM DR													
10+80.09	12+73.99	368				228	0.6	3		78			
HOLLIS DR													
9+75.00	19+16.01	4,139		3,495			2.7	14		391			
KOKO MILL RD													
24+15.14	27+68.24	382		257			2.1	11		308			
SUBTOTAL		71,400		8,620		44,375	339	6,810	116.5	613	13,437	4,831	17,254
HOLLIS EAST LIMITS TO 9+75 & COCKRELL													
HOLLIS DR													
25+23.22	28+08.34						0.9	5		127			
STA 28+08.34 BK = STA 0+00.00 AH													
0+00.00	3+66.85	1,674		1,425			1.1	6		160			
3+66.85	6+52.06	2,952		2,437			1.9	10		273			
6+52.06	9+75.00	1,504		1,297			1.0	5		145			
COCKRELL LN													
11+02.35	12+23.26						0.2	1		33			
12+23.26	13+14.10	511		480			0.4	2		54			
13+14.10	14+23.02	858		804			0.6	3		90			
14+23.02	18+60.40	2,396		2,093			1.6	9		234			
SUBTOTAL		9,895		8,536		0	0	0	7.7	41	0	0	1,116
HPR, TURN LANE AND BICYCLE LANE ON ARCHER													
ARCHER ELEVATOR RD													
11+42.19	14+66.85	721		721			0.5	3		81			
HPR / ARCHER ELEVATOR RD													
8+68.22	9+57.6	91		29			0.2	1		33			
SUBTOTAL		812		721		0	0	0	0.7	4	0	0	114
ADDITIONAL BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)													
MERCANTILE DR													
6+61.08	8+56.86	87		87			0.1	1		10			
SUBTOTAL		87		87		0	0	0	0.1	1	0	0	10
TOTALS		82,194		17,964		44,375	368	6,810	126.0	659	13,437	4,831	18,495

SURFACE REMOVAL - BUTT JOINT

STATION TO STATION	40600982	40600985
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT
	SO YD	
MAINLINE WABASH AVENUE		
WABASH AVE (FAU 8012)		
340+00.0	340+30.0	73.3
INTERNATIONAL PKWY		
12+25.98	12+40.98	60.1
BUNKER HILL RD & ASH GROVE RD		
12+27.18	12+42.18	59.4
ARCHER ELEVATOR RD		
17+33.15	18+0.15	169.5
PLEASANT RUN		
9+07.05	9+22.05	80.0
NORTH MEADOWBROOK RD		
11+70.95	11+85.95	57.3
SOUTH MEADOWBROOK RD		
63+35.15	63+50.15	59.9
SUBTOTAL		486.2
USE		74
HOLLIS EAST LIMITS TO 9+75 & COCKRELL LANE		
COCKRELL LN		
11+03.26	12+23.26	236.0
SUBTOTAL		236.0
USE		0
TOTAL		723

PROTECTIVE COAT

CONCRETE ITEM	42001300 PROTECTIVE COAT SO YD
MAINLINE WABASH AVENUE	
TY M-6.06 CURB AND GUTTER	82
TY M-6.12 CURB AND GUTTER	46
TY M-6.18 CURB AND GUTTER	11
TY M-6.24 CURB AND GUTTER	332
TY B-6.12 CURB AND GUTTER	85
TY B-6.18 CURB AND GUTTER	1197
TY B-6.24 CURB AND GUTTER	2565
CONCRETE GUTTER, TY B	65
TYPE B GUTTER OUTLET	18
CONCRETE MEDIAN SURFACE 4"	734
CONCRETE MEDIAN TY SM-6.06	451
CONCRETE MEDIAN TY SM-6.12	109
CONCRETE MEDIAN TY SM (DOWELLED)	1855
SUBTOTAL	7550
USE	7550
HOLLIS EAST LIMITS TO 9+75 & COCKRELL LANE	
COCKRELL LANE	
TY M-6.06 CURB AND GUTTER	16
TY M-6.24 CURB AND GUTTER	55
TY B-6.18 CURB AND GUTTER	875
CONCRETE MEDIAN SURFACE 4"	190
CONCRETE CURB, TY B (SPECIAL)	3
SUBTOTAL	1,139
USE	1,139
TOTAL	8,689

FILE NAME: c:\pwork\pwork\dot\edw\ds\d3736450	USER NAME: edwardsjd	DESIGNED: JMO	REVISED: JDE 2/21/2014	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU ROUTE 8012 (WABASH AVE) SCHEDULE OF QUANTITIES	F.A.U. R.T.E.: 8012	SECTION: 211W-3, TS-1, RS-7)	COUNTY: SANGAMON	TOTAL SHEETS: 679	SHEET NO.: 68
PLOT SCALE: 1/8"=1'-0"	CHECKED: AMW	REVISED: JDE 4/8/2014	SCALE: SHEET 5 OF 27 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				
PLOT DATE: Apr-08-2014 03:06:26PM	DATE: 12/4/2013	REVISED:	CONTRACT NO. 72890							
Default										

REV. 4-15-14