

DRAINAGE SCHEDULE

LOCATION	METAL END SECTIONS 12"	END SECTIONS 24"	PIPE CULV CLASS D, TY 1 15"	PIPE CULV CLASS D, TY 1 24"	PIPE CULV CLASS D, TY 1 24" (TEMP)	PIPE CULV CLASS A, TY 1 24"	PIPE DRAINS 12"	TYPE C INLET BOX STD 609006	TYPE D INLET BOX STD 609006	FLUSH INLET BOX FOR MEDIAN STD 542546	CONCRETE THRUST BLOCKS	INLET TY A TY 8 GRATE	MANHOLE TY A 4' DIA. TY 1 FRAME CLOSED LID
	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
WEST CROSSOVER - EB		2	16	594								1	2
WEST CROSSOVER - WB		2			300								
TEMPORARY ENTRANCE RAMP						10				1			
SN 026-0106 WEST APPROACH SLAB	2						68	1	1		1		
SN 026-0106 EAST APPROACH SLAB	2						68	1	1		1		
SN 026-0107 WEST APPROACH SLAB	1						13	1					
SN 026-0107 EAST APPROACH SLAB	2						68	1	1		1		
EAST CROSSOVERS		1	33	270								2	1
TOTALS	7	5	49	864	300	10	217	4	3	1	3	3	3

PIPE UNDERDRAIN SCHEDULE

LOCATION	CONCRETE HEADWALL REMOVAL	CONCRETE HEADWALLS FOR PIPE DRAINS	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN	PIPE UNDERDRAINS 4" (SPECIAL)	PIPE UNDERDRAINS FOR STRUCTURES 4"
	EACH	EACH	EACH	FOOT	FOOT
WEST CROSSOVER - EB	3	1		35	
WEST CROSSOVER - WB					
TEMPORARY ENTRANCE RAMP	1	1	1	15	
SN 026-0106 WEST ABUTMENT		1			75
SN 026-0106 EAST ABUTMENT		1			75
SN 026-0107 WEST ABUTMENT	1	2		5	75
SN 026-0107 EAST ABUTMENT	1	2			75
EAST CROSSOVERS	3	2		30	
TOTALS	9	10	1	85	300

PERMANENT SURVEY MARKERS SCHEDULE

LOCATION	PERMANENT SURVEY MARKERS, TYPE II
	EACH
PT STA 535+86.34	1
POT STA 551+00.00	1
TOTAL	2

TEMPORARY FENCE SCHEDULE

LOCATION	TEMPORARY FENCE
	FOOT
NORTHWEST QUADRANT	810
NORTHEAST QUADRANT	690
SOUTHWEST QUADRANT	790
SOUTHEAST QUADRANT	660
TOTAL	2950

PRINT DRIVER = L:\026-0106\01000005.dwg
SCALE NAME = PLOT
FILE NAME = D:\2014\026-0106\01000005.dwg



USER NAME = has	DESIGNED - ELH	REVISED -
ESCA PROJECT NO. 1000.05	DRAWN - HAS	REVISED -
PLOT SCALE = 0.1667' / IN.	CHECKED - RDP	REVISED -
PLOT DATE = 1/29/2014 1:37:08 PM	DATE - 11/13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-3B-1, 3B-1(3))BR	FAYETTE	277	23
CONTRACT NO. 74175				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				