

**PAVEMENT MARKING SCHEDULE**

LOCATION	DESCRIPTION	MODIFIED URETHANE PAVEMENT MARKING LINE 4"		MODIFIED URETHANE PAVEMENT MARKING LINE 8"		TEMPORARY PAVEMENT MARKING LINE 4"		SHORT TERM PAVEMENT MARKING (1 APPLICATION)		PREFORMED PLASTIC PAVEMENT MARKING TYPE B- LINE 6"	GROOVING FOR RECESSED PAVEMENT MARKING 5"		GROOVING FOR RECESSED PAVEMENT MARKING 9"
		FOOT		FOOT		FOOT		FOOT		FOOT	FOOT		FOOT
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	
BEFORE STAGE II													
SN 026-0085	SKIP DASH ☒					280		112					
SN 026-0085	EDGE LINE					1100	1100	48	48				
SN 026-0018	SKIP DASH ☒					280		112					
SN 026-0018	EDGE LINE					1100	1100	48	48				
AFTER STAGE II													
STA 529+05 TO STA 531+80, LT	EDGE LINE		280				280		16			280	
STA 535+10 TO STA 574+50, RT	EDGE LINE		3940				3940		164			3940	
STA 537+00 TO STA 550+50, LT	EDGE LINE	1350				1350		60			1350		
STA 537+00 TO STA 550+50	SKIP DASH ☒					340		136		340			
STA 577+50 TO STA 581+50, LT	EDGE LINE		400				400		20			400	
AFTER STAGE IV													
STA 487+00 TO STA 491+00, RT	EDGE LINE		400				400		16			400	
STA 487+00 TO STA 489+50	SKIP DASH ☒					70		28		70			
STA 494+00 TO STA 574+50, LT	EDGE LINE		8050				8050		328			8050	
STA 523+20 TO STA 526+50	SKIP DASH ☒					90		36		90			
STA 577+50 TO STA 581+50, RT	EDGE LINE		400				400		16			400	
EB ENTRANCE RAMP	EDGE LINE	1500		970		2470		1034			1500		970
EB ENTRANCE RAMP	EDGE LINE		300				300		16			300	
EB ENTRANCE RAMP	DOTTED LINE	170				170					170		
STA 1523+23 TO STA 1550+50, LT	EDGE LINE		2730				2730		116			2730	
STA 1523+23 TO STA 1550+50, RT	EDGE LINE	1580				1580		68			1580		
STA 1537+50 TO STA 1550+50	SKIP DASH ☒					330		132		330			
SUBTOTALS		4600	16500	970		9160	18700	1814	788	830	4600	16500	970
TOTALS		21100		970		27860		2602		830	21100		970

**RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE**

LOCATION	RRPM	RRPM (BRIDGE)	RRPM REMOVAL
	EACH	EACH	EACH
	WEST OF SN 026-0106	4	
EAST OF SN 026-0106	2		2
WEST OF SN 026-0107	14		14
EAST OF SN 026-0107	2		2
SN 026-0106		28	
SN 026-0107		28	
TOTALS	22	56	22

**WORK ZONE AND PAVEMENT MARKING REMOVAL SCHEDULE**

LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
		SQ FT	SQ FT
THROUGHOUT PROJECT	TEMPORARY PAVEMENT MARKING	7640	
THROUGHOUT PROJECT	SHORT TERM PAVEMENT MARKING	870	
STAGE II TRAFFIC CONTROL			
STA 529+30 TO STA 531+25, LT	EDGE LINE		65
STA 535+60 TO STA 573+60, RT	EDGE LINE		1270
STA 578+40 TO STA 581+50, LT	EDGE LINE		105
STAGE IV TRAFFIC CONTROL			
STA 487+00 TO STA 490+20, RT	EDGE LINE		110
STA 487+00 TO STA 489+50, RT	SKIP DASH ☒		35
STA 494+80 TO STA 573+70, LT	EDGE LINE		2630
STA 578+30 TO STA 581+50, RT	EDGE LINE		110
TOTALS		8510	4325

**TEMPORARY RAISED PAVEMENT MARKER SCHEDULE**

LOCATION	TEMPORARY RAISED PAVEMENT MARKER	
	WHITE	YELLOW
EACH		
STAGE IB TRAFFIC CONTROL		
WEST LANE SHIFT		51
EAST LANE SHIFT		51
STAGE II TRAFFIC CONTROL		
WEST LANE SHIFT		51
WEST CROSSOVER - WB	44	44
EAST CROSSOVERS	56	56
EAST LANE SHIFT		51
STAGE III TRAFFIC CONTROL		
WEST LANE SHIFT		51
EAST LANE SHIFT		51
STAGE IV TRAFFIC CONTROL		
WEST LANE SHIFT		51
WEST CROSSOVER - EB	56	56
TEMPORARY ENTRANCE RAMP	44	30
EAST CROSSOVERS	56	56
EAST LANE SHIFT		51
STAGE V TRAFFIC CONTROL		
WEST LANE SHIFT		51
EAST LANE SHIFT		51
SUBTOTALS		256 752
TOTAL		1008

PRINT DRIVER = L:\00-ESCA\011...  
 SCALE NAME = ...  
 FILE NAME = ...



USER NAME = has	DESIGNED - ELH	REVISED -
ESCA PROJECT NO. 1000.05	DRAWN - HAS	REVISED -
PLOT SCALE = 0.1667' / IN.	CHECKED - RDP	REVISED -
PLOT DATE = 2/19/2014 11:4:07 PM	DATE - 02/14	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-3B-1, 3B-1(3))BR	FAYETTE	277	24
CONTRACT NO. 74175			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	