

SUMMARY OF QUANTITIES				90% FED	10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 026-0106 & 0107
51202305	DRIVING PILES	FOOT	31393		31393
51500100	NAME PLATES	EACH	2		2
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	18		18
52100510	ANCHOR BOLTS, 3/4"	EACH	60		60
52100520	ANCHOR BOLTS, 1"	EACH	72		72
52100530	ANCHOR BOLTS, 1 1/4"	EACH	192		192
54213459	END SECTIONS 24"	EACH	5	5	
54215547	METAL END SECTIONS 12"	EACH	7	7	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1	
54248510	CONCRETE COLLAR	CU YD	0.6	0.6	
58700300	CONCRETE SEALER	SO FT	2891		2891
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	194		194
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	10	10	
60100945	PIPE DRAINS 12"	FOOT	217	217	

PRINTED AT: LEO E. SCHEIDT & ASSOCIATES, INC.  
 1000 N. WASHINGTON ST., SUITE 100, CHICAGO, IL 60610  
 TEL: 312.329.1000 FAX: 312.329.1001



USER NAME = h09  
 ESCA PROJECT NO. 1208.05  
 PLOT SCALE = 0.1667" / 1"  
 PLOT DATE = 1/29/2014 1:31:30 PM

DESIGNED - ELH  
 DRAWN - HAS  
 CHECKED - RDP  
 DATE - 01/14

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE SHEET NO. 5 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-38-1, 38-113)BR	FAYETTE	277	8
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74175	