

20200600 EXCAVATING AND GRADING EXISTING SHOULDER	48102100 AGGREGATE WEDGE SHOULDER, TYPE B	48203029 HOT-MIX ASPHALT SHOULDERS, 8"	64200108 SHOULDER RUMBLE STRIPS, 8 INCH	78001110 PAINT PAVEMENT MARKING - LINE 4"
---	---	--	---	---

STATION	TO	STATION	SIDE	LENGTH (FT)	UNIT	TON	SQ YD	FOOT	FOOT
3+19.00		181+85.00	RT/LT	17866.0	339.9	1290.2	11328.7	34682	35239
181+85.00		220+00.00	RT/LT	3815.0	-	183.7	-	-	6953
220+00.00		529+50.00	RT/LT	30950.0	571.5	2169.5	19049	58611	60740
529+50.00		532+44.00	RT/LT	294.0	-	19.6	-	588	588
532+44.00		687+15.00	RT/LT	15471.0	292.2	1109.2	9739.7	29998	30677
SHELBY COUNTY TOTALS =					1204	4772	40117	123879	134197
687+15.00		785+28.00	RT/LT	9813.0	187.6	712.3	6254.3	18185	19169
"SHUMWAY Y" @ CR 4			RT	206.0	2.1	7.8	68.7	206	206
807+60.00		871+19.00	RT/LT	6359.0	124.3	471.8	4143	12314	12485
EFFINGHAM COUNTY TOTALS =					314	1192	10466	30705	31860
PROJECT TOTALS =					1518	5964	50583	154584	166057

NOTE: THE EFFINGHAM COUNTY SECTION IS STAMPED IN METRIC STATIONING.
 STA. 687+15.00 = STA. 5+974.06
 STA. 785+28.00 = STA. 2+983.21
 STA. 807+60.00 = STA. 2+302.93
 STA. 871+19.00 = STA. 0+364.79

• D7 HMA SAFETY SHLD 2014-1
 ** SHELBY & EFFINGHAM