

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES
20200100	EARTH EXCAVATION	CU YD	89
20400800	FURNISHED EXCAVATION	CU YD	96
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1698
44003100	MEDIAN REMOVAL	SQ FT	7977
48101200	AGGREGATE SHOULDERS, TYPE B	TON	206
50300225	CONCRETE STRUCTURES	CU YD	22.8
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2270
60608250	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06	FOOT	867
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	831
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	11170
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3612.5
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	12.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	23
63200310	GUARDRAIL REMOVAL	FOOT	124
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
78200300	PRISMATIC CURB REFLECTORS	EACH	56
78200410	GUARDRAIL MARKERS, TYPE A	EACH	86
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	23
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.2
X6311217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	8
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -
o:\p\work\p\p\dat\staffennk\0365715\0774645-shr-SCG.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A | SHEET OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D7 SAFETY 2014-1	VARIOUS	20	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74645	