

PAVING SCHEDULE																	
LOCATION				EARTH EXCAVATION	FURNISHED EXCAVATION	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	PAVED SHOULDER REMOVAL	POLY HMA SURFACE COURSE, SMA, N80	POLY HMA BINDER COURSE, IL-19.0, FG, N90	BITUMINOUS MATERIALS (PRIME COAT)	HMA SHOULDERS (2")	HMA SHOULDERS (2.25")	HMA SHOULDERS (8")	HMA BASE COURSE, 11"	AGGREGATE WEDGE SHOULDER, TYPE B	HMA SURFACE <sup>3</sup> REMOVAL - BUTT JOINT	SHOULDER RUMBLE STRIPS, 16"
STA.	TO	STA.	RT/LT	CU YD	CU YD	SQ YD	SQ YD	TON	TON	POUND	TON	TON	SQ YD	SQ YD	TON	SQ YD	FOOT
I-70 WESTBOUND																	
2778+74.10	TO	3038+61.99				69301		7762	8732	49377		5093.6			621.8	146.7	23829
2797+21.28	TO	2806+18.28	LT				399							996.7			
2797+82.28	TO	2805+57.28	RT	100	617		861							861.1			
2800+19.78	TO	2803+19.78		267												44.4	
2839+16.22	TO	2848+13.22	LT				399							996.7			
2839+77.22	TO	2847+52.22	RT	100	617		861							861.1			
2842+14.72	TO	2845+14.72		267												44.4	
2999+10.88	TO	3008+07.88	LT				399							996.7			
2999+71.88	TO	3007+46.88	RT	100	617		861							861.1			
3002+09.38	TO	3005+09.38		267												44.4	
2970+95.03	TO	2977+10.03	RT	80	294			119					245				GAP
I-70 EASTBOUND																	
2778+74.10	TO	3038+61.99				69301		7762	8732	49377		5093.6			621.8	146.7	24758
2798+09.41	TO	2807+06.41	RT				399							996.7			
2798+70.41	TO	2806+45.41	LT				861							861.1			
2801+07.91	TO	2804+07.91		267												44.4	
2838+59.75	TO	2847+56.75	RT				399							996.7			
2839+20.75	TO	2846+95.75	LT				861							861.1			
2841+58.25	TO	2844+58.25		267												44.4	
2998+97.17	TO	3007+94.17	RT				399							996.7			
2999+58.17	TO	3007+33.17	LT				861							861.1			
3001+95.67	TO	3004+95.67		267												44.4	
2964+21.00	TO	2970+36.00	LT	80	294			121 <sup>1</sup>					245				GAP
3025+08.77	TO	3031+23.77	LT	80	294			354 <sup>2</sup>					245				GAP
MUL BERRY GROVE RAMPS																	
RAMP I - WB EXIT																	
03+03.15	TO	07+52.40						89		629	67.1				10.7	328.0	
RAMP II - EB ENTRANCE																	
11+75.41	TO	16+00.41						85		595	63.5				10.2	421.8	
RAMP III - EB EXIT																	
03+03.15	TO	07+52.40						89		629	67.1				10.7	409.8	
RAMP IV - WB ENTRANCE																	
07+49.97	TO	11+31.46						76		534	57.0				9.1	548.4	
TOTAL				2142	2733	138603	7560	16458	17465	101141	256	10188	735	11148	1285	2269	48588

NOTE: 1 THIS IS FOR ONE HALF THE CROSSOVER AREA. THE OTHER HALF IS COVERED UNDER THE OTHER DIRECTION.  
2 THIS IS FOR THE ENTIRE CROSSOVER AS THE WB APPROACH IS ALREADY BUILT.  
3 BUTT-JOINTS FOR THE AREA UNDER THE BRIDGES ARE FOR THE SHOULDER TIE-INS.