

PIPE UNDERDRAIN AND PIPE DRAIN SCHEDULE

ROADWAY	LOCATION		SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE UNDERDRAIN REMOVAL	PIPE UNDER-DRAINS, 6"	PIPE UNDER-DRAINS, 6" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS & SYMBOLS	OUTLET & HEADWALL 601101		REMARKS	
												STATION TO STATION
	FOOT INSIDE	FOOT INSIDE										FOOT INSIDE
FAI- 70 WB LT	2923+40	2928+00	460	481	460	21	1	2	2928+00	SUMMIT AT	2923+50 = RAMP I 5+36 RT	
	2928+04	2933+00	496	517	496	21	1	2	2933+00		PLUG AT	2928+04
	2933+04	2938+00	496	517	496	21	1	2	2938+00			2933+04
	2938+04	2943+00	496	517	496	21	1	2	2943+00			2938+04
	2943+04	2948+69	565	586	565	21	1	2	2948+69			2943+04
FAI 70 WB RT	2779+00	2784+00	500	521	500	21	1	2	2784+00	PLUG AT	2779+00	
	2784+04	2787+72	368	390	368	22	1	2	2787+72		2784+04 OUTLET INTO CULVERT HEADWALL	
	2787+76	2792+00	424	445	424	21	1	2	2792+00		2787+76	
	2792+04	2797+14	510	524	510	14	1	2	2797+14		2792+04 OUTLET INTO CULVERT WALL	
	2797+18	2802+00	482	503	482	21	1	2	2802+00		2797+18	
	2802+04	2807+00	496	517	496	21	1	2	2807+00		2802+04	
	2807+04	2812+00	496	517	496	21	1	2	2812+00		2807+04	
	2812+04	2817+00	496	517	496	21	1	2	2817+00		2812+04	
	2817+04	2822+00	496	517	496	21	1	2	2822+00		2817+04	
	2822+04	2827+00	496	517	496	21	1	2	TEE AT 2827+00		2822+04	
	2827+00	2827+96	96	96	96				2827+00		2827+96	
	2828+00	2832+96	496	517	496	21	1	2	2828+00		2832+96	
	2833+00	2837+40	440	461	440	21	1	2	2833+00		2837+40	
	2837+44	2841+96	452	476	452	24	1	2	2837+44		2841+96 OUTLET INTO CULVERT HEADWALL	
	2842+00	2845+96	396	417	396	21	1	2	2842+00		2845+96	
	2846+00	2849+96	396	417	396	21	1	2	2846+00		2849+96	
	2850+00	2853+74	374	395	374	21	1	2	2850+00		2853+74	
2853+78	2858+00	422	441	422	19	1	2	2853+78	2858+00 OUTLET INTO CULVERT HEADWALL			
2858+00	2863+00	500	521	500	21	1	2	2858+00	2858+00			
SUBTOTAL THIS SCHEDULE			10849	11327	10849	478	23	46				