

GUARDRAIL SCHEDULE

LOCATION	SIDE	STEEL PLATE BEAM GUARDRAIL REMOVAL (FT)	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' POSTS (FT)	TRAF BAR TERM, TYPE 1 SPECIAL FLARED (EACH)	TRAF BAR TERMINAL TYPE 6 (EACH)	TERMINAL MARKER - DA (EACH)	BARRIER WALL MARKERS, TYPE C (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)
LOC. 1 - FAP 690								
*REPLACEMENT MARKERS: SN 095-0038								8
LOC. 1 - FAS 819								
SN 095-2481 STA. 190+62	LT	150.0						
SN 095-2481 STA. 190+62	RT	150.0						
*REPLACEMENT MARKERS: SN 095-2482								8
*REPLACEMENT MARKERS: SN 095-2483								8
*REPLACEMENT MARKERS: SN 095-0066							8	7
*REPLACEMENT MARKERS: SN 095-2484								8
*REPLACEMENT MARKERS: STA. 522+94								8
LOC. 2 - FAS 819								
SN 095-2498 STA. 87+53.4	LT	100.0						
SN 095-2498 STA. 87+53.4	RT	100.0						
SN 095-0068 STA. 102+61	LT	145.0	50.0	1	1	1		2
*REPLACEMENT MARKERS							8	
SN 095-0068 STA. 98+12	RT	145.0	50.0	1	1	1		2
TOTALS		790.0	100.0	2	2	2	16	51

*FOR USE ON EXISTING GUARDRAIL OR CONCRETE BRIDGE PARAPET WHERE REPLACEMENT IS NEEDED.

MARKERS ARE SPACED AT 80' CENTERS (4 MINIMUM PER RUN). THIS APPLIES TO THE FIRST 400', THEN SPACING SHOULD BE INCREASED TO 400'. MARKERS ARE SPACED CLOSER ON CURVES PER STANDARD.

BARRIER WALL MARKERS SHALL BE PLACED ON THE TOP OF THE PARAPET WITH MARKER LOCATIONS TO INCLUDE THE FAR CORNERS OF THE BRIDGE.

FILE NAME =	USER NAME = milecmr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pwork\pwork\milecmr\d0345201\d07661-sht-plen.dgn		DRAWN -	REVISED -			•	(109,110)RS-1, 31-2RS	WASHINGTON	40	10	
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -			*FAP 690/FAS 819/FAP 322		CONTRACT NO. 76G61			
	PLOT DATE = 2/6/2014	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	