

				80% FED 20% STATE			
				CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOC. 1 FAP 690	LOC. 1 FAS 819	LOC. 2 FAS 819	LOC. 2 FAP 322
				WEST OF I-64	EAST OF I-64	IL 177 R1&2	RAMPS 3&4
				ROADWAY	ROADWAY	ROADWAY	ROADWAY
				0005	0005	0005	0005
				RURAL	RURAL	RURAL	RURAL
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.3	0.7		
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1			0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6		6		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	17865	1098	15693	815	259
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	166.4	93.6		72.8	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	143673	19769	108987	10605	4312
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200		200		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	60		60		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	214		124	45	45
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	50222.74	6805.27	38078	3783.47	1556
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	166.4	93.6		72.8	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	143673	19769	108987	10605	4312
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200		200		

* SPECIALTY ITEM

FILE NAME =	USER NAME = ml101omr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.*	SECTION	COUNTY	TOTAL	SHEET
ai\pvc_work\pwidet\ml101omr\d8345281\d076	g61-shr-plenudgn	DRAWN -	REVISED -						* 009,110RS-1, 31-2RS	WASHINGTON	40	5	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			*FAP 690/FAS 819/FAP 322	CONTRACT NO. 76G61							
PLOT DATE = 2/6/2014	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT	