

PAVEMENT AND SHOULDER SCHEDULE

LOCATION			PROCESSING MODIFIED SOIL 12"	LIME TON	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SUBBASE GRANULAR MATERIAL, TYPE C CU YD	AGGREGATE BASE COURSE, TYPE A 8"	BITUMINOUS MATERIALS (PRIME-COAT) POUND	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90 TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 10 3/4" SQ YD
STATION	TO	STATION	SQ YD		SQ YD	SQ YD		SQ YD					
DONNA DRIVE													
85+21.41	-	100+00.00	6566	162.5				6,446	3,992	871	520		
100+00.00	-	132+78.62	12866	318.4				12,368	7,377	1,666	994		
132+78.62	-	144+16.11							2,218			357	
SARA LANE													
8+20.00	-	10+00.00				508		487	243	64	38		
MAIN STREET SOUTH													
1+00.00	-	3+55.00	798	19.8			15		306				584
3+55.00	-	5+85.00	497	15.0			20						314
MAIN STREET NORTH													
0+00.00	-	15+07.50	5,439	134.6					3,618				4,423
0+65.22	-	0+75.76											
PLAZA DRIVE EAST													
126+47.01	-	126+72.01				79		77	41	9	5		
126+72.01	-	127+83.42				381		322	184	42	25		
SAMUEL ROAD													
6+00.00	-	10+90.00				1933		1,874		188	112		
15+42.43	-	17+24.52				966		946	328	105	62		
17+88.53	-	19+70.77				1029		993	328	113	67		
BRIGGS ROAD													
6+26.09	-	9+36.00	1,681	41.6				1,633	558	187	112		
10+00.00	-	11+48.74	723	17.9				714	268	79	47		
11+48.74	-	13+22.78	530	13.1				515	313	69	44		
BRIGGS ROAD SPUR													
100+00.00	-	102+70.00				825		794	486	105	63		
SHEET TOTALS			29,100	723	0	5,721	35	27,189	20,260	3,497	2,089	357	5,321
SHEET TOTALS FROM PVMT SCH 01-02			72,218	1,787	80,383	2,241	860	27,728	6,820	3,724	2,224	645	28,494
SHEET TOTALS FROM DWY SCH-22					2,003				486				
SHEET TOTALS FROM DWY SCH-23					658				16				
PROJECT TOTALS			101,318	2,510	83,045	7,962	895	54,897	27,583	7,222	4,313	1,002	33,815

△ REV. 4-16-14

FILE NAME =	USER NAME = colenn	DESIGNED - KH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT AND SHOULDER SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\pvd\colenn\8363810\097021-sh4-SCH-03.dgn		DRAWN - AS	REVISED -			331	(1-3R-2, H-4, TS-4, HBK-1)	WILLIAMSON	733	45
PLOT SCALE = 2.8888 * / in.		CHECKED -	REVISED -			DRAWING NO.	SCH-03	CONTRACT NO.	78221	
PLOT DATE = 4/16/2014		DATE -	REVISED -			SCALE:	SHEET NO. 3 OF 56 SHEETS	STA.	TO STA.	(ILLINOIS) FED. AID PROJECT

(1-3R-2, H-4, TS-4, HBK-1)