

SIDEWALK SCHEDULE

LOCATION			PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH 50 FT	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH 50 FT	DETECTABLE WARNINGS 50 FT	REMARKS
STATION	TO	STATION				
WOLF CREEK ROAD						
90+38.79	-	98+60.08		9,429.5	60.0	
100+75.92	-	103+25.70		2,695.5	20.0	
103+25.70	-	109+67.28		6,841.0	40.0	
NORTH FRONTAGE ROAD						
22+55.43	-	27+25.23		4,639.5	10.0	
27+25.23	-	28+01.14		579.0	10.0	
50+75.00	-	52+25.85		1,317.5	14.0	
52+25.85	-	53+83.13		1,198.0	14.0	
53+83.13	-	69+59.77		15,242.0	140.0	
69+59.77	-	74+40.74		4,872.0		
74+40.74	-	96+51.25		21,952.0	50.0	
96+51.25	-	97+02.92		1,250.0	200.0	
97+02.92	-	104+95.83		7,547.5	40.0	
104+95.83	-	111+62.48		6,560.5	20.0	
MAIN STREET NORTH						
5+84.08	-	14+78.52		3,880.5	10.0	
PROJECT TOTALS			3,880.5	84,124.0	628.0	

BOLLARD SCHEDULE

LOCATION		FOLD DOWN BOLLARDS		BOLLARDS
STATION	OFFSET	EACH	EACH	EACH
WOLF CREEK ROAD				
91+17.00	37.90 LT			1
91+19.17	42.47 LT	1		
91+21.37	47.04 LT			1
95+66.59	48.12 LT			1
95+64.91	52.71 LT	1		
95+63.27	57.32 LT			1
96+64.97	37.00 LT			1
96+64.97	42.00 LT	1		
96+64.97	47.00 LT			1
102+63.49	37.00 LT			1
102+63.49	42.00 LT	1		
102+63.49	47.00 LT			1
103+69.05	51.51 LT			1
103+71.42	55.92 LT	1		
103+73.79	60.32 LT			1
108+93.55	52.80 LT			1
108+91.75	57.47 LT	1		
108+89.94	62.13 LT			1
NORTH FRONTAGE ROAD				
26+74.06	45.58 LT			1
26+75.68	40.85 LT	1		
26+77.30	36.12 LT			1
28+01.14	30.00 LT			1
28+01.14	25.00 LT	1		
28+01.14	20.00 LT			1
51+65.30	50.79 LT			1
51+66.89	46.05 LT	1		
51+68.49	41.31 LT			1
53+08.84	36.00 LT			1
53+08.84	31.00 LT	1		
53+08.84	26.00 LT			1
68+41.21	31.80 LT			1
68+42.21	26.90 LT	1		
68+43.20	22.00 LT			1
69+31.21	34.00 LT			1
69+31.21	29.00 LT	1		
69+31.21	24.00 LT			1
96+11.75	47.50 LT			1
96+11.75	42.50 LT	1		
96+11.75	37.50 LT			1
97+02.61	37.50 RT			1
97+02.61	42.50 RT	1		
97+02.61	47.50 RT			1
102+14.05	56.73 RT			1
102+14.13	61.73 RT	1		
102+14.22	66.73 RT			1
102+78.04	55.87 RT			1
102+78.13	60.87 RT	1		
102+78.22	65.87 RT			1
111+41.44	19.00 RT			1
111+41.44	24.00 RT	1		
111+41.44	29.00 RT			1
PROJECT TOTALS		17		34

2

2 Rev. 4-21-14