



**LEGEND**

- ① - THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS
- ② - THERMOPLASTIC PAVEMENT MARKING - LINE 4"
- ③ - THERMOPLASTIC PAVEMENT MARKING - LINE 12"
- ④ - THERMOPLASTIC PAVEMENT MARKING - LINE 24"
- A - DENOTES STANDARD SIGN PANELS (SEE NOTE 1)
- N-1 - DENOTES NON-STANDARD SIGN PANELS (SEE NOTE 1)
- ⑤ - PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS
- ⑥ - PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"
- ⑦ - PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"
- ⑧ - PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"
- ⑨ - PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"
- ⑩ - RAISED REFLECTIVE PAVEMENT MARKERS
- ▲ - PROPOSED SIGNS

**NOTES:**

1. FOR PROPOSED SIGN PANEL LAYOUT AND DIMENSIONS, SEE SIGN PANEL DETAILS.
2. PROPOSED SIGN OFFSET IS MEASURED FROM CENTERLINE OF SPECIFIED ROAD TO THE SIGN CENTER UNLESS OTHERWISE NOTED.
3. FOR A SUMMARY OF SIGN REMOVALS, SEE REMOVAL SCHEDULES.
4. DOUBLE YELLOW CENTERLINE PAVEMENT MARKING DETAIL WITH PC, PT AND RADIUS SHALL BE PLACED AT A SPLIT OF PAVEMENT EDGES.
5. SIGNING FOR IL-13 AND BRIGGS ROAD FROM STA 7+50 TO STA 12+00 IS COVERED ON PM-04 (BOTTOM).
6. SIGNING FOR NORTH FRONTAGE ROAD AT BRIGGS ROAD IS COVERED ON PM-19 (BOTTOM) AND PM-20 (TOP).

FILE NAME =	USER NAME = \$USER\$	DESIGNED - KN	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT MARKING AND SIGNING PLANS BRIGGS ROAD</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw\work\p\dot\lavenderba\d0363618\0978221-sht\pmk-27.dgn		DRAWN - AS	REVISED -			331	(1-3)R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	338	
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -			<b>DRAWING NO. PM-27</b>	<b>CONTRACT NO. 78221</b>				
PLOT DATE = 1/31/2014		DATE -	REVISED -			SCALE:	SHEET NO. 27 OF 28 SHEETS	STA. 6+26.09 TO STA. 32+00	ILLINOIS FED. AID PROJECT		