

STAGE 3 SHOULDER SCHEDULE

LOCATION STATION TO STATION			COMMENTS	PAVED SHOULDER WIDTH	SHOULDER DEPTH	PCC SHOULDER 12"	HMA SHOULDERS	AGG. SHLDRS, TY. A 8"	SHLDR RUMBLE STRIP	BIT MATLS (PRIME COAT)
				FT	INCH	SQ YD	TON	SQ YD	FOOT	POUNDS
STAGE 3										
2356+80.00	TO	2360+00.00	EB I-64 (I64) IL & IS (BUTT JOINT)	8	8	X	133	71	320	128
2360+00.00	TO	2363+46.36	EB I-64 (I64) IL & IS	8	8	X	144	77	346	139
2364+03.81	TO	2371+96.95	EB I-64 TO SB I-57 (I5764C) IL & WIDENING & IS	8	8	X	329	176	793	317
2371+96.95	TO	2378+60.38	EB I-64 TO SB I-57 (I5764C) IL & IS & WIDENING (SHLD)	8*	8	X	267	X	663	268
2378+60.38	TO	2395+58.04	EB I-64 TO SB I-57 (I5764C) IL & IS	8	8	X	704	377	1698	679
2395+58.04	TO	2398+72.60	EB I-64 TO SB I-57 (I5764C) IL	X	X	X	X	X	X	X
839+34.91	TO	843+66.07	SB I-57 (TAPERC1) IL	X	X	X	X	X	X	X
874+42.33	TO	877+23.31	SB I-57 TO WB I-64 (TAPERF2) DL (WIDENING) & OS	10	8	X	145	X	281	140
871+92.38	TO	874+42.33	SB I-57 TO WB I-64 (TAPERF2) DL & OS	10	8	X	129	X	250	125
+18.94	TO	2+24.76	SB I-57 TO WB I-64 (I5764F) DL & OS	10	8	X	106	X	206	103
2+24.76	TO	5+44.76	SB I-57 TO WB I-64 (I5764F) DL & OS & IS (transition)	18	8 TO 2	X	183	X	640	288
5+44.76	TO	9+71.11	SB I-57 TO WB I-64 (I5764F) DL & OS & IS	18	2	X	96	X	853	384
9+71.11	TO	12+91.11	SB I-57 TO WB I-64 (I5764F) DL & OS & IS (transition)	18	8 TO 2	X	183	X	640	288
12+91.11	TO	14+43.93	SB I-57 TO WB I-64 (I5764F) DL & OS	10	8	X	79	X	153	76
+.	TO	2+43.26	EB I-64 TO NB I-57 (I5764E) DL & IS	8	8	X	101	X	243	97
2+43.26	TO	5+63.26	EB I-64 TO NB I-57 (I5764E) DL & IS & OS, PATCH & R/S (transition)	18	8 TO 2	X	183	X	640	288
5+63.26	TO	9+76.76	EB I-64 TO NB I-57 (I5764E) DL & IS & OS, PATCH & R/S	18	2	X	93	X	827	372
13+15.79	TO	17+55.20	EB I-64 TO NB I-57 (I5764E) DL & IS & OS, PATCH & R/S	18	2	X	99	X	879	395
17+55.20	TO	20+75.20	EB I-64 TO NB I-57 (I5764E) DL & IS & OS, PATCH & R/S (transition)	18	8 TO 2	X	183	X	640	288
20+75.20	TO	23+64.17	EB I-64 TO NB I-57 (I5764E) DL & IS	8	8	X	120	X	289	116
2372+03.74	TO	2375+85.32	EB I-64 TO NB I-57 (TAPERE1) DL & IS	8	8	X	158	X	382	153
*SHOULDER WIDTH VARIES				SUBTOTAL STAGE 3		0	3436	702	10742	4645
				TOTAL STAGE 3		0	10392	1231	23419	11254

△ REV. 4-10-14

FILE NAME =	USER NAME = rollvr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STAGE 3 SHOULDER SCHEDULE	PLAN RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
at\pzw\work\spc\rollvr\10270968\7827	rollvr\pzw\sch\10270968	DRAWN -	REVISED -			**	.	JEFFERSON	235	37	
#MODELNAME#	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			
	PLOT DATE = 4/4/2014	DATE -	REVISED -			CONTRACT NO. 78276		**57/64			