

CROSSROAD CULVERT FILL HEIGHT

STATION		ESTIMATED FILL (FT)	DESCRIPTION
833+98.38	I-57 NB (I5764B)	26.13	66" RCP
843+98.18	I-57 NB (I5764B)	3.53	24" RCP
851+00	I-57 NB (I5764B)	2.85	24" RCP
866+20 & 2+50	I-57 NB (I5764B) & RAMP E (I5764E)	10.57	36" RCP
883+00	I-57 NB & SB (I5764A)	2.08	24" RCP
834+10	SB I-57 (I5764A)	26.71	54" RCP
850+00	SB I-57 (I5764A)	1.79	36" RCP
868+90 & 3+00	SB I-57 (I5764A) & RAMP F (I5764F)	2.41	30" RCP
2366+00	RAMP C (I5764C)	3.57	24" RCP

FILL WAS ESTIMATED FROM THE TOP OF PIPE TO TOP OF EXISTING PAVEMENT
IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY FIELD CONDITIONS.