

STAGE 4 PAVEMENT SCHEDULE

LOCATION STATION TO STATION			COMMENTS	LANE WIDTH	CRC PAVEMENT 12"	PROC MOD SOIL 12"	LIME	PAVEMENT REINF	STAB SUBBASE 4"	POLY HMA SURF CSE, MIX E	POLY HMA BINDER COURSE	HMA BINDER COURSE	BIT MATLS (PRIME COAT)	POLY BIT MATLS (PC)	RUBBLIZE PCC PVMT	BRIDGE APPR PVT CONN-PCC
				FT	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	TON	TON	GAL	GAL	SQ YD	SQ YD
STAGE 4																
834+91.42	TO	838+11.42	NB I-57 (I5764B) IL & IS (BUTT JOINT)	12	X	X	X	X	X	49	33	20	13	25	X	X
838+11.42	TO	844+71.86	NB I-57 TO WB I-64 (TAPERD1) IL & IS	12	X	X	X	X	X	100	113	389	X	X	881	X
2364+05.07	TO	2382+54.88	NB I-57 TO WB I-64 (I5764D) IL & IS	12	X	X	X	X	X	280	316	1090	X	X	2466	X
2382+54.88	TO	2385+74.88	NB I-57 TO WB I-64 (I5764D) IL & IS (transition)	12	X	X	X	X	X	48	70	53	X	X	X	X
2388+50.04	TO	2391+70.04	NB I-57 TO WB I-64 (I5764D) IL & IS (transition)	12	X	X	X	X	X	48	70	53	X	X	X	X
2391+70.04	TO	2403+05.51	NB I-57 TO WB I-64 (I5764D) IL & IS	12	X	X	X	X	X	172	194	669	X	X	1514	X
2360+00.00	TO	2363+46.36	WB I-64 (I64) IL & IS	12	X	X	X	X	X	52	59	204	X	X	462	X
2356+80.00	TO	2360+00.00	WB I-64 (I64) IL & IS (BUTT JOINT)	12	X	X	X	X	X	49	33	20	13	25	X	X
833+05.03	TO	836+25.03	SB I-57 (I5764A) IL & IS (BUTT JOINT)	12	X	X	X	X	X	49	33	20	13	25	X	X
836+25.03	TO	878+00.00	SB I-57 (I5764A) IL & IS	12	X	X	X	X	X	632	712	2460	X	X	5567	X
878+00.00	TO	881+20.00	SB I-57 (I5764A) IL & IS, PATCH & R/S (transition)	12	X	X	X	X	X	42	78	80	25	13	X	X
881+20.00	TO	885+00.00	SB I-57 (I5764A) IL & IS, PATCH & R/S	12	X	X	X	X	X	43	65	X	X	46	X	X
TOTAL STAGE 4					0	0	0	0	0	1,567	1,774	5,056	65	134	10,889	0