

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FUNDING:	
				90% FED 10% STATE	
				LOCATION:	
		URBAN			
		ROUTE:	FAI 57 I-57	FAI 64 I-64	
			ROADWAY 0004	ROADWAY 0004	
20100500	TREE REMOVAL, ACRES	ACRE	5.6	1.4	4.2
20200100	EARTH EXCAVATION	CU YD	9155	5535	3620
20400100	BORROW EXCAVATION	CU YD	32331	15291	17040
25000200	SEEDING, CLASS 2	ACRE	29.1	14.2	14.9
25000350	SEEDING, CLASS 7	ACRE	29.1	14.2	14.9
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5235	2552	2683
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2618	1276	1342
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2618	1276	1342
25000700	AGRICULTURAL GROUND LIMESTONE	TON	58	28	30
25100115	MULCH, METHOD 2	ACRE	58	28	30
25100630	EROSION CONTROL BLANKET	SQ YD	140,744	68,597	72,147
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	8725	4252	4473
28000305	TEMPORARY DITCH CHECKS	FOOT	4924	3056	1868
28000400	PERIMETER EROSION BARRIER	FOOT	16,825	9900	6925

FILE NAME *	USER NAME # *USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cl:\pwork\pwork\dot\kell\kell\0278968\782	6-sha-ovr-req.index.dgn	DRAWN -	REVISED -			**	*	JEFFERSON	235	11
#MODELNAME*	PLOT SCALE * 1/8"=200' / 1"=100'	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT DATE * 2/7/2014	DATE -	REVISED -							
								ILLINOIS FED. AID PROJECT		CONTRACT NO. 78276