SUMMARY OF QUANTITIES - CONT

FUNDING:	90% FED 10% STATE	
LOCATION:	URBAN	
ROUTE:	FAI 57 I-57	FAI 64 I-64

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	ROADWAY 0004
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	17708	17708	
30201500	LIME	TON	526	526	
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	17708	17708	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4612	1561	3051
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	879	458	421
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1424	996	428
40603092	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	TON	22,988	10448	12,540
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	7795	3543	4252
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	7294	3240	4054
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2062	2062	
42100340	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	10830	10830	
42100615	PAVEMENT REINFORCEMENT	SQ YD	10830	10830	
42101300	PROTECTIVE COAT	SQ YD	13,212	13,212	
42101436	LUG SYSTEM COMPLETE 36'	EACH	3	3	