






• ADJUST AS NEEDED TO MATCH INTO EXISTING PAVEMENT MARKING

EROSION CONTROL NOTES

1. THE CONTRACTOR WILL BE REQUIRED TO IMPLEMENT AND MAINTAIN EROSION CONTROL MEASURES IMMEDIATELY AFTER STRIPPING OF EXISTING VEGETATION.
2. STOCKPILES OF SOIL AND OTHER BUILDING MATERIALS TO REMAIN IN PLACE MORE THAN THREE (3) DAYS SHALL BE FURNISHED WITH EROSION AND SEDIMENT CONTROL MEASURES (I.E. PERIMETER SILT FENCE). STOCKPILES TO REMAIN IN PLACE FOR 14 DAYS OR MORE SHALL RECEIVE TEMPORARY SEEDING.
3. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PREVENT POLLUTION OF STORM WATER AND SHALL FOLLOW IEPA REGULATIONS & IDOT CONSTRUCTION MEMORANDUM NO. 06-60.
4. STABILIZATION MEASURES SHALL BE INITIATED WITHIN 7 DAYS OF CONSTRUCTION ACTIVITY TEMPORARILY OR PERMANENTLY CEASING IN AREAS WHERE IT WILL NOT OCCUR FOR A PERIOD OF 14 OR MORE CALENDAR DAYS.
5. THE SOIL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE INSPECTED WEEKLY AND AFTER 1/2 INCH OF RAIN OR MORE BY THE INDIVIDUAL ON SITE IN CHARGE OF SOIL EROSION AND SEDIMENT CONTROL DURING THE CONSTRUCTION OF THE PROJECT.
6. SILT FENCE SHALL BE INSTALLED FOLLOWING THE COMPLETION AND STABILIZATION OF THE STORMWATER FACILITIES AND WILL REMAIN IN PLACE UNTIL THE CONTRIBUTING AREA IS STABILIZED.
7. ALL ADJACENT STREETS MUST BE KEPT CLEAR OF DEBRIS. INSPECTED DAILY AND CLEANED WHEN NECESSARY OR AS DIRECTED BY THE ENGINEER.
8. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE REFERENCED FROM THE ILLINOIS URBAN MANUAL.

LEGEND

-  FINAL RESTORATION OF DISTURBED AREAS
- TOPSOIL FURNISH AND PLACE, 4"
- SEEDING CLASS 2A
- EROSION CONTROL BLANKET
-  INLET AND PIPE PROTECTION
-  PERIMETER EROSION BARRIER
-  DIRECTION OF FLOW/GRADING



COMPANY NAME: HRGreen
 PROJECT CONTACT: Kevin M. Artz
 CLIENT: City of Rockford
 DATE PLOTTED: 2/20/2014 10:04:48 AM
 FILE NAME: 06130054-Striping.dgn
 PLOT NUMBER: 06130054-Striping.dgn
 PLOT TABLE: STRIPING


 HRGreen.com
 3000 Professional Design Firm
 #194-001322

USER NAME = kwhood	DESIGNED - KMA	REVISED -
FILE NAME = 06130054-Striping.dgn	DRAWN - WJH	REVISED -
PLOT SCALE = 1"=20'	CHECKED - RDC	REVISED -
PLOT DATE = 2/28/2014	DATE - 2/20/14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RAILROAD AVENUE OVER KEITH CREEK
STRIPING, EROSION CONTROL, AND RESTORATION PLAN

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

M.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3259	11-00590-00-BR	WINNEBAGO	32	10
CONTRACT NO. 65607				

FED. ROAD DIST. NO. 2 | ILLINOIS | FED. AID PROJECT