

COUNTY	SECTION	HWY.NO.	SHEET NO.
LASALLE	15-00326-00-WR	29	6 of 16

Contract # 87566

GUARDRAIL SCHEDULE							
LOCATION		GUARDRAIL REMOVAL	S.P.B.G.R., TYPE A, 6 FOOT POSTS	S.P.B.G.R. (SHORT RADIUS)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6 (MODIFIED)
STATION	SIDE	FOOT	FOOT	FOOT	EACH	EACH	EACH
15+43-17+72	LT	293.5	200.0	-	2	-	-
15+99-17+71	RT	193.4	112.5	10.0	1	1	-
59+60-60+43	LT	196.0	87.5	37.5	2	-	-
60+67-62+87	LT	286.4	212.5	-	2	-	-
60+88-68+37	RT	742.8	650.0	-	1	-	1
67+23-68+41	LT	113.0	25.0	-	1	-	1
71+32-76+35	RT	503.1	437.5	-	1	-	1
71+39-76+53	LT	527.2	450.0	20.5	1	1	1
89+62-91+24	RT	155.0	100.0	-	2	-	-
89+66-91+24	LT	187.7	137.5	-	2	-	-
100+60-102+62	LT	201.5	150.0	-	2	-	-
100+61-102+61	RT	199.8	150.0	-	2	-	-
TOTAL		3,599	2,712.5	68	19	2	4

PAINT PAVEMENT MARKING				
STATION	SIDE	WHITE EDGE LINE	YELLOW SKIP DASH	YELLOW SOLID LINE
		FOOT	FOOT	FOOT
9+00 TO 60+42	LT	5,142	-	-
9+00 TO 9+87	RT	159	-	-
9+00 TO 13+03	℄	-	151	-
10+12 TO 34+40	RT	2,493	-	-
13+03 TO 20+41	℄ - NORTH BOUND	-	-	738
13+03 TO 20+41	℄ - SOUTH BOUND	-	277	-
20+41 TO 24+00	℄	-	135	-
24+00 TO 31+37	℄ - NORTH BOUND	-	276	-
24+00 TO 31+37	℄ - SOUTH BOUND	-	-	737
31+37 TO 33+75	℄	-	89	-
33+75 TO 44+76	℄ - NORTH BOUND	-	-	1,101
33+75 TO 44+76	℄ - SOUTH BOUND	-	413	-
35+00 TO 49+88	RT	1,488	-	-
44+76 TO 106+65	℄ - NORTH BOUND	-	-	6,189
44+76 TO 106+65	℄ - SOUTH BOUND	-	-	6,189
50+87 TO 103+50	RT	5,263	-	-
61+26 TO 89+06	LT	2,780	-	-
89+90 TO 116+79	LT	2,689	-	-
104+37 TO 116+79	RT	1,242	-	-
106+65 TO 116+78	℄ - NORTH BOUND	-	380	-
106+65 TO 116+78	℄ - SOUTH BOUND	-	-	1,013
116+78 TO 168+95	℄	-	1,956	-
117+83 TO 168+23	LT	5,040	-	-
117+83 TO 168+23	RT	5,040	-	-
TOTALS		31,336	3,677	15,967