

EARTHWORK SUMMARY						
LOCATION	20200100		20201200		20700110	
	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT
	CU YD	CU YD	CU YD	CU YD	CU YD	TONS
TENNESSE BLACKTOP NORTH	86	64	21	43		
TENNESSE BLACKTOP NORTH - IL ROUTE 9	87	65	36	29	0	0
TENNESSE BLACKTOP SOUTH	352	264	11	253	0	0
CONTINGENCY	0	0	0	0	50	100
TOTAL	525	393	68	325	50	100

EROSION CONTROL SCHEDULE							
LOCATION	21101625 TOPSOIL FURNISH AND PLACE, 6"	25100630 EROSION CONTROL BLANKET	25100635 HEAVY DUTY EROSION CONTROL BLANKET	28000250 TEMPORARY EROSION CONTROL SEEDING	XX006343 SEEDING (COMPLETE)	XX008871 MULCH	
							BEGIN STATION
TENNESSEE BLACKTOP							
10+35.00	13+38.19	569	282	85	12	569	232
30+15.66	33+15.00	223	0	0	5	223	223
TOTAL		792	282	85	17	792	455

CURB OUTLET SCHEDULE					
LOCATION	STATION	OFFSET	LT/RT	XX024058 OUTLET SPECIAL EACH	XX006529 CONCRETE CURB AND GUTTER END OUTLET SPECIAL EACH
30+42.92	47.49		RT	1	
30+46.58	19.98		LT		1
31+44.39	14.31		RT		1
TOTAL					3

PAVEMENT, SIDEWALK, CURB, AND SHOULDER SCHEDULE										
LOCATION	31100500 SUBBASE GRANULAR MATERIAL, TYPE A 6"	40200800 AGGREGATE SURFACE COURSE, TYPE B	42000110 PORTLAND CEMENT CONCRETE PAVEMENT 6 1/2"	42001300 PROTECTIVE COAT	42400100 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	48101200 AGGREGATE SHOULDERS, TYPE B	X4200840 PORTLAND CEMENT CONCRETE INLAY, 4"	X6061815 COMBINATION CONCRETE CURB AND GUTTER, TYPE M (SPECIAL)	XX007371 PORTLAND CEMENT CONCRETE PAVEMENT, FURNISHED	
										BEGIN STATION
TENNESSEE BLACKTOP										
10+35.00	13+38.19	252	0	252	995	0	110	743	0	83
30+15.66	33+15.00	1168	35	1105	1175	64	60	0	169	0
TOTAL		1420	35	1357	2170	64	170	743	169	83
FROM COLD IN-PLACE RECYCLING SCHEDULE						5200				
TOTAL						5370				

COLD IN-PLACE RECYCLING SCHEDULE							
LOCATION	48101200 AGGREGATE SHOULDERS, TYPE B	70300100 SHORT TERM PAVEMENT MARKING	LR400005 CIR-FDR EMULSIFIED ASPHALT	LR400760 COLD IN-PLACE RECYCLING, 6.0"	LR403300 SURFACE PROFILE MILLING	XX004450 BITUMINOUS SURFACE TREATMENT, A-2 SPECIAL	
							BEGIN STATION
TENNESSEE BLACKTOP RECYCLING SECTION							
		5200	5200	258,471	116656	116656	
TOTAL		5200	5200	258,471	116656	116656	
FROM PAVEMENT, SIDEWALK, CURB, AND SHOULDER SCHEDULE		170					
TOTAL		5370					

REMOVAL SCHEDULE						
LOCATION	44000100 PAVEMENT REMOVAL	44000165 HOT-MIX ASPHALT SURFACE REMOVAL, 4"	44000600 SIDEWALK REMOVAL	44004000 PAVED DITCH REMOVAL	XX000714 FENCE TO BE REMOVED AND RE-ERECTED	
						BEGIN STATION
TENNESSEE BLACKTOP						
10+35.00	13+38.19	103	776	0	0	67
30+15.66	33+15.00	941	0	74	43	0
TOTAL		1044	776	74	43	67

PAVEMENT MARKING SCHEDULE				
LOCATION	78001110 PAINT PAVEMENT MARKING - LINE 4"	78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	78009024 MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	
				BEGIN STATION
TENNESSEE BLACKTOP				
10+35.00	13+38.19	0	547	21
30+15.66	33+15.00	0	551	18
RECYCLING SECTION		35445	0	0
TOTAL		35445	1098	39

SIGN REMOVAL SCHEDULE					
LOCATION	STATION	OFFSET	SIDE	X7240300 SIGN REMOVAL EACH	
					13+05.40
13+06.61	21.27		RT	1	
30+34.49	20.26		LT	1	
TOTAL					3

SIGN SCHEDULE						
LOCATION	STATION	OFFSET	LT/RT	72000100 SIGN PANEL - TYPE 1 SQ FT	72900100 METAL POST - TYPE A FOOT	
						13+01.01
30+40.02	23.92		LT	9.0	13.5	
TOTAL					18	27

REMOVAL AND ADJUSTMENT SCHEDULE						
LOCATION	60500040 REMOVING MANHOLES EACH	X8026050 SANITARY MANHOLES TO BE ADJUSTED EACH	STATION	OFFSET		
					LT/RT	EACH
30+35.24	29.22		RT	1		
30+21.51	23.95		LT	1		
TOTAL					1	1

PERIMETER EROSION BARRIER SCHEDULE			
LOCATION	28000400 PERIMETER EROSION BARRIER	FEET	
			10+34.98
10+34.94	12+60.72	226.5	
31+23.00	33+15.00	207.0	
31+86.41	33+15.00	131.0	
TOTAL			860

INLET FILTERS SCHEDULE				
LOCATION	STATION	OFFSET	28000510 INLET FILTERS EACH	
				13+20.11
30+50.51	22.09		LT	1
30+35.24	29.22		RT	1
30+42.92	47.49		RT	1
TOTAL				4

TEMPORARY DITCH CHECK SCHEDULE				
LOCATION	STATION	OFFSET	28000305 TEMPORARY DITCH CHECK FOOT	
				12+60.72
3+60.76	20.72		RT	10
TOTAL				21

JMM 5/25/2013
 JMM 1/17/2014
 KNS 1/20/2014

FILE NAME = J:\11\Jobs\111016\CAD\Road\Sheet\c-081sch.dgn	USER NAME = monsh01398	DESIGNED - JMM	REVISED -
PLOT SCALE = 10.0000 1 / in.	PLOT DATE = 01/20/2014	DRAWN - JMM	REVISED -
		CHECKED - KNS	REVISED -
		DATE - 1/21/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TENNESSEE BLACKTOP (CH 11)
SCHEDULE OF QUANTITIES

SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	F.A.S. RTE. 1434	SECTION 11-00101-00-RS	COUNTY MCDONOUGH	TOTAL SHEETS 33	SHEET NO. 7
CONTRACT NO. 89607						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT RS 1434 (106)	