

SUMMARY OF QUANTITIES

ROUTE NO	SECTION	COUNTY	TOTAL SHEETS	THIS SHEET
LOCAL STREET	*	TAEWELL	23	3

FED. RD. DIST. NO. 7 ILLINOIS PROJECT
 12-00112-00-SW
 CONTRACT NO. 89623

CODE NUMBER	ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	SP
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	12	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	78	
20200100	EARTH EXCAVATION	CU.YD.	94	
20400800	FURNISHED EXCAVATION	CU.YD.	304	*
20800150	TRENCH BACKFILL	CU.YD.	149	
25000100	SEEDING, CLASS 1	ACRE	0.30	*
25000400	NITROGEN FERTILIZER NUTRIENT	LB	27	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	LB	27	
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	27	
25100115	MULCH METHOD 2	ACRE	0.30	
28000400	PERIMETER EROSION BARRIER	FOOT	517	
28000500	INLET AND PIPE PROTECTION	EACH	3	
28000510	INLET FILTERS	EACH	6	
28100125	STONE RIPRAP, CLASS B3	SQ.YD.	14	
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 8 INCH	SQ.YD.	171	
△ 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25	
△ 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE "C", N50	TON	28	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ.YD.	296	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ.FT.	2,649	
44000100	PAVEMENT REMOVAL	SQ.YD.	158	*
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ.YD.	286	*
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	36	
50105220	PIPE CULVERT REMOVAL	FOOT	164	*
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION, 12"	EACH	2	
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	338	
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	262	
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	34	
55100500	STORM SEWER REMOVAL, 12"	FOOT	81	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	*
60500060	REMOVING INLETS	EACH	1	
60603800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-8.12	FOOT	599	*
67100100	MOBILIZATION	L.SUM	1	
X6020082	INLETS, TYPE G-1	EACH	2	*
X6021814	INLET MANHOLE, TYPE G-1, 4' DIAMETER	EACH	4	*
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L.SUM	1	*
<i>X8008934</i>	<i>RELOCATE EXISTING SCHOOL SPEED LIMIT FLASHER</i>	L.SUM	1	*

* SPECIAL PROVISIONS
 △ SPECIALTY ITEMS

SUMMARY OF QUANTITIES			AUSTIN ENGINEERING CO., INC. Consulting Engineers & Surveyors 6100 North University Street Peoria, Illinois 61615-1879 License No. 1264001143
BEVERLY MANOR SCHOOL SIDEWALK			
FOR: CITY OF WASHINGTON		DATE	PROJECT
DATE 12/19/13	SCALE	DATE 12/20-12-009	SHEET NO. 3 OF 23