

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1350
20800150	TRENCH BACKFILL	CU YD	148
25000100	SEEDING, CLASS 1	ACRE	0.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18
25100115	MULCH, METHOD 2	ACRE	0.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20
28000400	PERIMETER EROSION BARRIER	FOOT	165
28000500	INLET AND PIPE PROTECTION	EACH	23
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	5919
30201500	LIME	TON	146
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	5919
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	138
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	17
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	9
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	4878
42001200	PAVEMENT FABRIC	SQ YD	4878
42001300	PROTECTIVE COAT	SQ YD	6787
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	11
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	229
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6418
42400800	DETECTABLE WARNINGS	SQ FT	145
44000100	PAVEMENT REMOVAL	SQ YD	4960
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	142
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2470
44000600	SIDEWALK REMOVAL	SQ FT	5710

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
44003100	MEDIAN REMOVAL	SQ FT	1244
44004000	PAVED DITCH REMOVAL	FOOT	59
50901760	PIPE HANDRAIL	FOOT	76
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	128
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	77
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	251
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	3
55100300	STORM SEWER REMOVAL 8"	FOOT	46
55100500	STORM SEWER REMOVAL 12"	FOOT	18
55100700	STORM SEWER REMOVAL 15"	FOOT	72
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	5
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	3
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	6
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	4
60260100	INLETS TO BE ADJUSTED	EACH	1
60500060	REMOVING INLETS	EACH	6
60600605	CONCRETE CURB, TYPE B	FOOT	65
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1974
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	84
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1241
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ FT	370
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	18
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1871

* SPECIALTY ITEMS